


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

T R EW sec 1/4 1/4 1/4 No.

Kansas State Dept. Of Health
(Water Well Contractors)
Forbes-Bldg. 740
Topeka, Kansas 66620

1 Location of well:	County Pottawatomie	Township name Belvue	Fraction 1/4 NE4, NE4	Section number 3	Town number T10S	Range number R11E
Distance and direction from nearest town or city: East of Belvue between US24 & UPRR Tracks Street address of well location if in city:				3 Owner of well: Kansas Power & Light Co. Jeffrey Energy Center Address: Belvue, Kansas		
Locate with "X" in section below: N  W S 1 Mile				4 Well depth: 65.40' ft. Date of completion 7/26/75 Well diameter 42" in.		
2 Type and color of material				5 <input type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary		
				6 Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input checked="" type="checkbox"/> Industry <input type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Commercial <input type="checkbox"/> Test well <input type="checkbox"/>		
Top soil				7 Casing: Material Stl Height: above/below 28 in. Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface 28 in. Diam. 24 in. to 35.40 ft. depth Drive shoe? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No		
				8 Screen: Manufacturer Layne Type St. stl. Dia. 24" Slot/gauze 0.105" Length 30' Set between 33 ft. and 63 ft. Fittings: 1/8" - 3/8" Gravel pack <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No Size range of material		
Brown clay				9 Static water level: 14 ft. below land surface Date 7/22/75		
Med. to coarse sand & med. gravel				10 Pumping level below land surfaces: 22 ft. after 2 hrs. pumping 1000 g.p.m. 23 ft. after 168 hrs. pumping 1000 g.p.m. Estimated maximum yield 1800 g.p.m.		
Fine to coarse sand & med. gravel				11 Water sample submitted: <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No Date 8/4/75		
Med. to coarse sand & gravel w/rocks				12 Well head completion: 24" <input checked="" type="checkbox"/> Pitless adapter <input type="checkbox"/> Inches above grade		
Blue shale				13 Well grouted? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> Neat cement <input checked="" type="checkbox"/> Bentonite <input type="checkbox"/> Depth: From 0 ft. to 20 ft.		
				14 Nearest source of possible contamination: ft. 2600 Direction W. Type W. Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No		
				15 Pump: <input type="checkbox"/> Not installed Manufacturer's name Layne Model number 11M2 HP 150 Volts 440 Length of drop pipe 35 ft. capacity 800 g.p.m. Type: <input checked="" type="checkbox"/> Submersible <input type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other		
(use a second sheet if needed)						
16 Remarks: elevation Approx. 959.36 Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input type="checkbox"/> Upland <input checked="" type="checkbox"/> Valley				17 Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Layne Western Co. 102 Business name License No. Address Wichita, Kansas Signed [Signature] Date 8/1/75		

Forward the white, blue and pink copies to the Kansas State Dept. Of Health.

Form WWC-5