

USE TYPEWRITER OR BALL  
POINT PEN-PRESS FIRMLY,  
PRINT CLEARLY.

WATER WELL RECORD  
KSA 82a-1201-1215

Kansas Department of Health and  
Environment-Division of Environment  
(Water well Contractors)  
Topeka, Kansas 66620

1. Location of well:	County <b>Pottawatomie</b>	Fraction <b>E 1/2 X NW 1/4</b>	Section number <b>11</b>	Township number <b>T 10S</b>	Range number <b>S R 11E E/W</b>
Distance and direction from nearest town or city: <b>1 1/4 miles E. &amp; 1/2 mile South &amp; 1/2 mile West of Belvue, Kansas</b>		3. Owner of well: <b>Pessmier Co.</b>			
Street address of well location if in city:		R.R. or street: City, state, zip code: <b>St. Marys, Kansas 66536</b>			
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. <b>32</b> in. Completion date <b>1-20-76</b> Well depth <b>77</b> ft.	
				7. Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary	
5. Type and color of material		From		To	
<b>Top soil &amp; fine sand</b>		<b>0'</b>		<b>18'</b>	
<b>Medium Brown gravel</b>		<b>18'</b>		<b>38'</b>	
<b>Medium green gravel</b>		<b>38'</b>		<b>77'</b>	
<b>Stopped on large rock</b>		<b>77'</b>			
				8. Use: Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input type="checkbox"/> <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other	
				9. Casing: Material <input type="checkbox"/> Height: Above or below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface <b>24</b> in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight <input type="checkbox"/> lbs./ft. Dia. <b>16</b> in. to <b>4</b> ft. depth Wall thickness <b>290</b> inches or Dia. <input type="checkbox"/> in. to <input type="checkbox"/> ft. depth gage No. <input type="checkbox"/>	
				10. Screen: Manufacturer's name <b>Doerr</b> Type <b>2" x 5/16"</b> Dia. <b>16</b> Slot/gauze <b>36</b> Length <b>36</b> Set between <b>41</b> ft. and <b>77</b> ft. ft. and <input type="checkbox"/> ft. Gravel pack? <input checked="" type="checkbox"/> Size range of material <b>5/8</b>	
				11. Static water level: <b>30</b> ft. below land surface Date <b>1-21-76</b>	
				12. Pumping level below land surfaces: <b>36</b> ft. after <b>1</b> hrs. pumping <b>1000</b> g.p.m. <b>39</b> ft. after <b>3</b> hrs. pumping <b>1200</b> g.p.m. Estimated maximum yield <b>2000</b> g.p.m.	
				13. Water sample submitted: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date <input type="checkbox"/>	
				14. Well head completion: <input type="checkbox"/> Pitless adapter <input type="checkbox"/> Inches above grade	
				15. Well grouted? <b>yes</b> With: <input type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input checked="" type="checkbox"/> Concrete Depth: From <b>0</b> ft. to <b>10</b> ft.	
				16. Nearest source of possible contamination: ft. <b>5</b> mile Direction <b>South</b> Type <b>River</b> Well disinfected upon completion? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	
				17. Pump: <input checked="" type="checkbox"/> Not installed Manufacturer's name <input type="checkbox"/> Model number <input type="checkbox"/> HP <input type="checkbox"/> Volts <input type="checkbox"/> Length of drop pipe <input type="checkbox"/> ft. capacity <input type="checkbox"/> g.p.m. Type: <input type="checkbox"/> Submersible <input type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other	
				(Use a second sheet if needed)	
18. Elevation:	19. Remarks: <b>Well is for flood irrigation and has drainage to the East.</b>		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <b>Hoobler Drilling Co.</b> <b>323</b> Business name <b>St. Marys, Kans. 66536</b> License No. Address <b>Don Hoobler</b> <b>1-22-76</b> Signed <b>Don Hoobler</b> Date <b>1-22-76</b> Authorized representative		
Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input type="checkbox"/> Upland <input checked="" type="checkbox"/> Valley					

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5