


USE TYPEWRITER OR BALL POINT PEN-PRESS FIRMLY, PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

SE SE NE

| | | | | | | |
|--|--|------------------------------|---|---|--|-------------------------------------|
| 1. Location of well: | | County Leavenworth | Fraction NW NE SW <i>1/4 1/4 1/4</i> | Section number 10 | Township number T 10 S R | Range number 22 <i>EW</i> |
| 2. Distance and direction from nearest town or city: Street address of well location if in city: NW corner of Fairmount Kansas | | | 3. Owner of well: R.R. or street: Pat Baliko 1921 N. 138th City, state, zip code: Kansas City, Kansas 66109 | | | |
| 4. Locate with "X" in section below: Sketch map:  | | | 6. Bore hole dia. <u>8</u> in. Completion date <u>7-22-77</u> Well depth <u>130</u> ft. | | | |
| 5. Type and color of material | | | From | To | 7. Cable tool <input checked="" type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input type="checkbox"/> Reverse rotary | |
| Top Soil | | | 0 | 3 | 8. Use: <input checked="" type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other | |
| Clay | | | 3 | 15 | 9. Casing: Material <u>Pl.</u> Height: Above or below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface <u>18</u> in. RMP <input type="checkbox"/> PVC <input checked="" type="checkbox"/> Weight _____ lbs./ft. Dia. <u>5</u> in. to <u>131</u> ft. depth; Wall Thickness: inches or Dia. _____ in. to _____ ft. depth; Gauge No. <u>.265</u> | |
| Sand & Gravel | | | 15 | 22 | 10. Screen: Manufacturer's name (<u>Slotted Pipe</u>) <u>Vinylplex, Inc.</u> Type <u>PVC</u> Dia. <u>5"</u> Slot/gauze <u>.06 1/16</u> Length <u>28'</u> Set between <u>92</u> ft. and <u>120</u> ft. Gravel pack? <input checked="" type="checkbox"/> Size range of material <u>1/4 - 1/8</u> | |
| Sandstone - Gray | | | 22 | 60 | 11. Static water level: _____ mo./day/yr. <u>50</u> ft. below land surface Date <u>7-22-77</u> | |
| Sandy Shale - Blue | | | 60 | 85 | 12. Pumping level below land surfaces: _____ ft. after _____ hrs. pumping _____ g.p.m. _____ ft. after _____ hrs. pumping _____ g.p.m. Estimated maximum yield <u>20</u> g.p.m. | |
| Sandstone - Gray | | | 85 | 90 | 13. Water sample submitted: _____ mo./day/yr. Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> Date _____ | |
| Sandy Shale - Blue | | | 90 | 92 | 14. Well head completion: <input checked="" type="checkbox"/> Pitless adapter <u>18</u> inches above grade | |
| Sandstone - Gray | | | 92 | 120 | 15. Well grouted? <u>Yes</u> With: <input checked="" type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input type="checkbox"/> Concrete Depth: From <u>3</u> ft. to <u>15</u> ft. | |
| Lime - White | | | 120 | 130 | 16. Nearest source of possible contamination: ft. <u>100'</u> Direction <u>east</u> Type <u>septic</u> Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No | |
| (Use a second sheet if needed) | | | | | 17. Pump: Not installed Manufacturer's name <u>Jacuzzi</u> Model number <u>354B</u> HP <u>1/2</u> Volts <u>220</u> Length of drop pipe <u>125</u> ft. capacity <u>10</u> g.p.m. Type: <input checked="" type="checkbox"/> Submersible <input type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other | |
| 18. Elevation: | | 19. Remarks: | | 20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. BREUER, INC. <u>174</u> Business name _____ License No. _____ Address <u>Box 117, Basehor, Ks. 66008</u> Signed: <u>Thomas A. Breuer</u> Date <u>7/25/77</u> Author (authorized representative) | | |

10 220 10
T
R
W
Sec
1/4
NE SE