

USE TYPEWRITER OR BALL POINT PEN-PRESS FIRMLY, PRINT CLEARLY.

WATER WELL RECORD  
KSA 82a-1201-1215

Kansas Department of Health and Environment-Division of Environment  
(Water well Contractors)  
Topeka, Kansas 66620

1. Location of well: County <u>Leavenworth</u> Fraction <u>SW 1/4 Sec 14 NE 1/4</u> Section number <u>33</u> Township number <u>T 10 S R 22</u> Range number <u>EW</u>																																														
2. Distance and direction from nearest town or city: <u>2 W - 4 S</u> Street address of well location if in city: <u>Bascher, KS</u>																																														
3. Owner of well: <u>Howard Jones</u> R.R. or street: <u>RR 1</u> City, state, zip code: <u>Bascher, Kans.</u>																																														
4. Locate with "X" in section below: Sketch map: <div style="display: flex; align-items: center;"> <div style="margin-right: 20px;"> </div> <div> </div> </div>																																														
5. Type and color of material <table border="1" style="width:100%; border-collapse: collapse;"> <thead> <tr> <th style="width: 80%;"></th> <th style="width: 10%;">From</th> <th style="width: 10%;">To</th> </tr> </thead> <tbody> <tr><td><u>T.S</u></td><td><u>0</u></td><td><u>2</u></td></tr> <tr><td><u>Blue Clay</u></td><td><u>2</u></td><td><u>13</u></td></tr> <tr><td><u>Sandy Clay</u></td><td><u>13</u></td><td><u>24</u></td></tr> <tr><td><u>Gray Clay</u></td><td><u>24</u></td><td><u>24</u></td></tr> <tr><td><u>Brown Sand Stone</u></td><td><u>26</u></td><td><u>33</u></td></tr> <tr><td><u>Fine Sand</u></td><td><u>33</u></td><td><u>35</u></td></tr> <tr><td><u>Fine Sand Stone</u></td><td><u>35</u></td><td><u>52</u></td></tr> <tr><td><u>Coarse Sand Stone</u></td><td><u>52</u></td><td><u>53</u></td></tr> <tr><td><u>yellow lime</u></td><td><u>53</u></td><td><u>54</u></td></tr> <tr><td><u>Gray lime</u></td><td><u>54</u></td><td><u>64</u></td></tr> <tr><td><u>Shale</u></td><td><u>64</u></td><td><u>68</u></td></tr> <tr><td><u>lime</u></td><td><u>68</u></td><td><u>73</u></td></tr> <tr><td><u>Shale</u></td><td><u>73</u></td><td><u>90</u></td></tr> <tr><td><u>lime</u></td><td><u>90</u></td><td><u>100</u></td></tr> </tbody> </table>			From	To	<u>T.S</u>	<u>0</u>	<u>2</u>	<u>Blue Clay</u>	<u>2</u>	<u>13</u>	<u>Sandy Clay</u>	<u>13</u>	<u>24</u>	<u>Gray Clay</u>	<u>24</u>	<u>24</u>	<u>Brown Sand Stone</u>	<u>26</u>	<u>33</u>	<u>Fine Sand</u>	<u>33</u>	<u>35</u>	<u>Fine Sand Stone</u>	<u>35</u>	<u>52</u>	<u>Coarse Sand Stone</u>	<u>52</u>	<u>53</u>	<u>yellow lime</u>	<u>53</u>	<u>54</u>	<u>Gray lime</u>	<u>54</u>	<u>64</u>	<u>Shale</u>	<u>64</u>	<u>68</u>	<u>lime</u>	<u>68</u>	<u>73</u>	<u>Shale</u>	<u>73</u>	<u>90</u>	<u>lime</u>	<u>90</u>	<u>100</u>
	From	To																																												
<u>T.S</u>	<u>0</u>	<u>2</u>																																												
<u>Blue Clay</u>	<u>2</u>	<u>13</u>																																												
<u>Sandy Clay</u>	<u>13</u>	<u>24</u>																																												
<u>Gray Clay</u>	<u>24</u>	<u>24</u>																																												
<u>Brown Sand Stone</u>	<u>26</u>	<u>33</u>																																												
<u>Fine Sand</u>	<u>33</u>	<u>35</u>																																												
<u>Fine Sand Stone</u>	<u>35</u>	<u>52</u>																																												
<u>Coarse Sand Stone</u>	<u>52</u>	<u>53</u>																																												
<u>yellow lime</u>	<u>53</u>	<u>54</u>																																												
<u>Gray lime</u>	<u>54</u>	<u>64</u>																																												
<u>Shale</u>	<u>64</u>	<u>68</u>																																												
<u>lime</u>	<u>68</u>	<u>73</u>																																												
<u>Shale</u>	<u>73</u>	<u>90</u>																																												
<u>lime</u>	<u>90</u>	<u>100</u>																																												
6. Bore hole dia. <u>10</u> in. Completion date _____ Well depth <u>100</u> ft. <u>2-1-76</u>																																														
7. <input type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input type="checkbox"/> Reverse rotary																																														
8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other																																														
9. Casing: Material <u>PVC</u> Height: Above or below Threaded _____ Welded _____ Surface <u>24</u> in. RMP _____ PVC <u>4</u> Weight <u>2.75</u> lbs./ft. Dia. <u>2</u> in. to <u>100</u> ft. depth Wall Thickness: inches or Dia. _____ in. to _____ ft. depth gage No. <u>223</u>																																														
10. Screen: Manufacturer's name <u>Purco</u> <u>11117</u> Type <u>PVC</u> Dia. <u>5</u> Slot/gauze <u>0.25</u> Length <u>35</u> Set between <u>25</u> ft. and <u>25</u> ft. <u>45</u> ft. and <u>100</u> ft. Gravel pack? <input checked="" type="checkbox"/> Size range of material <u>0.25/0.60</u>																																														
11. Static water level: _____ mo./day/yr. <u>20</u> ft. below land surface Date _____																																														
12. Pumping level below land surfaces: <u>Auto Test</u> _____ ft. after _____ hrs. pumping _____ g.p.m. _____ ft. after _____ hrs. pumping _____ g.p.m. Estimated maximum yield <u>1</u> g.p.m.																																														
13. Water sample submitted: _____ mo./day/yr. <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date <u>6-1-76</u>																																														
14. Well head completion: <u>Cap Top</u> <input type="checkbox"/> Pitless adapter <u>24</u> Inches above grade																																														
15. Well grouted? <input checked="" type="checkbox"/> With: <input type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input checked="" type="checkbox"/> Concrete Depth: From <u>0</u> ft. to <u>10</u> ft.																																														
16. Nearest source of possible contamination: ft. <u>200</u> Direction <u>SE</u> Type <u>backroad</u> Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No																																														
17. Pump: <input checked="" type="checkbox"/> Not installed Manufacturer's name _____ Model number _____ HP _____ Volts _____ Length of drop pipe _____ ft. capacity _____ g.p.m. Type: <input type="checkbox"/> Submersible <input type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other																																														
(Use a second sheet if needed)																																														
18. Elevation: <u>915</u> Topography: <input checked="" type="checkbox"/> Hill <input type="checkbox"/> Slope <input type="checkbox"/> Upland <input type="checkbox"/> Valley	19. Remarks: <u>I will put cement slab around the well</u>																																													
20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <u>Sigales Duty Co Inc 182</u> Business name _____ License No. _____ Address <u>RT 1 Hutton, KS</u> Signed <u>Wade Nelson</u> Date <u>6-25-76</u> Authorized representative																																														