

USE TYPEWRITER OR BALL POINT PEN-PRESS FIRMLY, PRINT CLEARLY.

WATER WELL RECORD  
KSA 82a-1201-1215

Kansas Department of Health and Environment-Division of Environment  
(Water well Contractors)  
Topeka, Kansas 66620

1. Location of well:		County <b>Leavenworth</b>	Fraction <b>SW 1/4 NW 1/4 SW 1/4</b>	Section number <b>5</b>	Township number <b>T 10 S R 23</b>	Range number <b>EW</b>
2. Distance and direction from nearest town or city: <b>1 1/2 miles south of</b>			3. Owner of well: <b>Mr. Charles Christ</b>			
Street address of well location if in city: <b>Lansing, Kansas</b>			R.R. or street: <b>1524 N. 34th</b>			
			City, state, zip code: <b>Kansas City, Kansas 66102</b>			
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. <b>8</b> in. Completion date <b>11-26-78</b>		
N		W		Well depth <b>140</b> ft.		
E		S		7. <input checked="" type="checkbox"/> Cable tool <input checked="" type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug		
1 Mile		1 Mile		<input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input type="checkbox"/> Reverse rotary		
1 Mile		1 Mile		8. Use: <input checked="" type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry		
1 Mile		1 Mile		<input type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock		
1 Mile		1 Mile		<input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other		
1 Mile		1 Mile		9. Casing: Material <b>PI</b> Height: Above or below		
1 Mile		1 Mile		Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface <b>18</b> in.		
1 Mile		1 Mile		RMP <input type="checkbox"/> PVC <input checked="" type="checkbox"/> Weight <input type="checkbox"/> lbs./ft.		
1 Mile		1 Mile		Dia. <b>5</b> in. to <b>14 1/4</b> depth Wall Thickness: inches or		
1 Mile		1 Mile		Dia. <input type="checkbox"/> in. to <input type="checkbox"/> ft. depth Gage No. <b>265</b>		
5. Type and color of material		From	To	10. Screens: Manufacturer's name <b>(Slotted Pipe)</b>		
<b>Top Soil</b>		<b>0</b>	<b>1</b>	<b>Vynplex, Inc.</b>		
<b>Clay</b>		<b>1</b>	<b>12</b>	Type <b>PVC</b> Dia. <b>5"</b>		
<b>Sandstone - Yellow</b>		<b>12</b>	<b>16</b>	Slot/gauze <b>06 1/16</b> Length <b>40'</b>		
<b>Shale - Yellow</b>		<b>16</b>	<b>20</b>	Set between <b>100</b> ft. and <b>140</b> ft.		
<b>Sandstone - Yellow</b>		<b>20</b>	<b>28</b>	Gravel pack? <input checked="" type="checkbox"/> Size range of material <b>1/4 - 1/8</b>		
<b>Sandy Shale - Light Blue</b>		<b>28</b>	<b>60</b>	11. Static water level: <b>70</b> ft. below land surface Date <b>11-26-78</b>		
<b>Sandstone - Yellow</b>		<b>60</b>	<b>100</b>	12. Pumping level below land surfaces:		
<b>Sandstone - Gray</b>		<b>100</b>	<b>140</b>	____ ft. after ____ hrs. pumping ____ g.p.m.		
				____ ft. after ____ hrs. pumping ____ g.p.m.		
				Estimated maximum yield <b>20</b> g.p.m.		
				13. Water sample submitted: <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No Date		
				14. Well head completion: <input checked="" type="checkbox"/> Pitless adapter <b>18</b> inches above grade		
				15. Well grouted? <b>Yes</b>		
				With: <input checked="" type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input type="checkbox"/> Concrete		
				Depth: From <b>3</b> ft. to <b>15</b> ft.		
				16. Nearest source of possible contamination: <b>100'</b> Direction <b>South</b> Type <b>Septic</b>		
				Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No		
				17. Pump: <input type="checkbox"/> Not installed		
				Manufacturer's name <b>Jacuzzi</b>		
				Model number <b>75UB</b> HP <b>3/4</b> Volts <b>220</b>		
				Length of drop pipe <b>130</b> ft. capacity <b>10</b> g.p.m.		
				Type:		
				<input checked="" type="checkbox"/> Submersible <input type="checkbox"/> Turbine		
				<input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating		
				<input type="checkbox"/> Centrifugal <input type="checkbox"/> Other		
(Use a second sheet if needed)						
18. Elevation: <b>2700</b>	19. Remarks:			20. Water well contractor's certification:		
Topography: <b>A</b>				This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.		
<input type="checkbox"/> Hill				<b>BREUER, INC.</b> <b>171</b>		
<input type="checkbox"/> Slope				Business name <b>Box 147, Basehor, Ks. 66007</b> License No.		
<input type="checkbox"/> Upland				Address <b>Box 147, Basehor, Ks. 66007</b>		
<input type="checkbox"/> Valley				Signed <b>[Signature]</b> Date <b>11-28-78</b>		