

USE TYPEWRITER OR BALL POINT PEN-PRESS FIRMLY, PRINT CLEARLY.

WATER WELL RECORD  
KSA 82a-1201-1215

Kansas Department of Health and Environment-Division of Environment  
(Water well Contractors)  
Topeka, Kansas 66620

1. Location of well:		County <b>WYANDOTTE</b>	Fraction <b>SE 1/4 SE 1/4 SE 1/4</b>	Section number <b>14</b>	Township number <b>T 10 Souths</b>	Range number <b>R 24 East/W</b>
2. Distance and direction from nearest town or city: <b>2 MILES NORTH OF KANSAS CITY, KANSAS</b> Street address of well location if in city: <b>NEARMAN POWER PLANT</b>				3. Owner of well: <b>SHARP BROS INC</b> R.R. or street: <b>1014 E 19th ST</b> City, state, zip code: <b>KANSAS CITY, MO 64108</b>		
4. Locate with "X" in section below: N W E S 1 Mile				Sketch map: 		
5. Type and color of material				From	To	
Top Soil				0	3	
Clay				3	10	
FINE S. LTY SAND				10	37	
FINE MED SAND w/ GR				37	52	
FINE SAND / SOME GRAVEL				52	58	
MED-FINE SAND				58	63	
COARSE SAND				63	68	
MED SAND				68	70	
(Use a second sheet if needed)						
6. Bore hole dia. <b>30</b> in. Completion date Well depth <b>70</b> ft. <b>9-16-78</b>		7. Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input checked="" type="checkbox"/> Bored <input type="checkbox"/> Reverse rotary				
8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input checked="" type="checkbox"/> Other		9. Casing: Material <b>STEEL</b> Height: Above or below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface <b>18</b> in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight _____ lbs./ft. Dia. <b>12</b> in. to <b>30</b> ft. depth Wall Thickness: inches or Dia. _____ in. to _____ ft. depth gauge No. <b>219</b>				
10. Screen: Manufacturer's name <b>JOHNSON SCREEN</b> Type <b>IRRIGATOR</b> Dia. <b>12"</b> Slot/gauze <b>.025</b> Length <b>40</b> Set between <b>30</b> ft. and <b>70</b> ft. _____ ft. and _____ ft. Gravel pack? <input checked="" type="checkbox"/> Size range of material <b>38 GR</b>		11. Static water level: _____ mo./day/yr. <b>16</b> ft. below land surface Date <b>9-17-78</b>				
12. Pumping level below land surfaces: <b>38</b> ft. after <b>48</b> hrs. pumping <b>400</b> g.p.m. _____ ft. after _____ hrs. pumping _____ g.p.m. Estimated maximum yield <b>400</b> g.p.m.		13. Water sample submitted: _____ mo./day/yr. <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date _____				
14. Well head completion: <input type="checkbox"/> Pitless adapter <b>18</b> inches above grade		15. Well grouted? <b>NO</b> With: <input type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input type="checkbox"/> Concrete Depth: From _____ ft. to _____ ft.				
16. Nearest source of possible contamination: ft. _____ Direction _____ Type _____ Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No		17. Pump: _____ Not installed Manufacturer's name <b>LAYNE BOWLER</b> Model number _____ HP <b>25</b> Volts <b>480</b> Length of drop pipe <b>60</b> ft. capacity <b>400</b> g.p.m. Type: <input checked="" type="checkbox"/> Submersible <input type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other				
18. Elevation: Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input type="checkbox"/> Upland <input checked="" type="checkbox"/> Valley		19. Remarks: <b># 8 - DEWATERING</b>		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <b>MOETREUCH AMERICAN</b> Business name _____ License No. _____ Address <b>DOWNERS GROVE, ILL</b> Signed <b>[Signature]</b> Date <b>2-79</b> Authorized representative		

T 10 S 14 SE SE SE