

USE TYPEWRITER OR BALL POINT PEN-PRESS FIRMLY, PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:	County Wyandotte	Fraction SE 1/4 NE 1/4 NE 1/4	Section number 13	Township number T 10-S	Range number S R 24	E WEST
2. Distance and direction from nearest town or city: West - 5 mi ±			3. Owner of well: Shawnee Const. Co.			
Street address of well location if in city:			R.R. or street: 6319 Kansas Avenue			
			City, state, zip code: Kansas City, KS 66111			
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. 30 in. Completion date 5-16-77		
N		1		Well depth 100 ft.		
W 1 Mile ↑ ↓ 1 Mile	NW	NE				
	SW	SE	E			
S		1 Mile		7. <input type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary		
5. Type and color of material		From	To	8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input checked="" type="checkbox"/> Other		
clay		0	10	9. Casing: Material steel Height: Above or below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface 2' above RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight 33 lbs./ft. Dia. 16 in. to 70 ft. depth Wall Thickness: inches or Dia. <input type="checkbox"/> in. to <input type="checkbox"/> ft. depth gage No. 3/4"		
Brown Med. Fine Sand		10	50	10. Screen: Manufacturer's name Doerr		
Medium coarse sand with gravel layers		50	100	Type punched Dia. 16" Slot/gauze 1/16" Length 30 Set between 70 ft. and 100 ft. ft. and <input type="checkbox"/> ft. Gravel pack? <input checked="" type="checkbox"/> Size range of material 1/4"		
				11. Static water level: <input type="checkbox"/> mo./day/yr. 16 ft. below land surface Date 5-16-77		
				12. Pumping level below land surfaces: 50 ft. after 10 hrs. pumping 1500 g.p.m. <input type="checkbox"/> ft. after <input type="checkbox"/> hrs. pumping <input type="checkbox"/> g.p.m. Estimated maximum yield 1500 g.p.m.		
				13. Water sample submitted: <input type="checkbox"/> mo./day/yr. <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date <input type="checkbox"/>		
				14. Well head completion: Temp. Dis. head <input type="checkbox"/> Pitless adapter <input type="checkbox"/> Inches above grade		
				15. Well grouted? no With: <input type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input type="checkbox"/> Concrete Depth: From <input type="checkbox"/> ft. to <input type="checkbox"/> ft.		
				16. Nearest source of possible contamination: ft. <input type="checkbox"/> Direction <input type="checkbox"/> Type <input type="checkbox"/> Well disinfected upon completion? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No		
				17. Pump: <input type="checkbox"/> Not installed Manufacturer's name Aurora Model number <input type="checkbox"/> HP 60 Volts <input type="checkbox"/> Length of drop pipe 60 ft. capacity 7000 g.p.m. Type: <input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other		
				(Use a second sheet if needed)		
18. Elevation:	19. Remarks:		20. Water well contractor's certification:			
Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input type="checkbox"/> Upland <input checked="" type="checkbox"/> Valley	Our contract with Shawnee states "All holes shall be filled to the satisfaction of the owner and/or engineers at no cost to our firm."		This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Southern Wellpoint Co., Inc. #235 Business name Address 2935 North Toledo, Tulsa, OK License No. <input type="checkbox"/> Signed A.W. Macomber Date 7-1-77 Authorized representative			

Forward the white, blue and pink copies to the Department of Health and Environment

A.W. Macomber, President
Form WWC-5