


USE TYPEWRITER OR BALL POINT PEN-PRESS FIRMLY, PRINT CLEARLY.

WATER WELL RECORD  
KSA 82a-1201-1215

Kansas Department of Health and Environment-Division of Environment (Water well Contractors) Topeka, Kansas 66620

1. Location of well:	County <b>Wyandotte</b>	Fraction <b>NE 1/4 NE 1/4 NE 1/4</b>	Section number <b>13</b>	Township number <b>T 10S</b>	Range number <b>S R 24</b>	<b>8/W</b>	
2. Distance and direction from nearest town or city: Street address of well location if in city:			3. Owner of well: <b>Shawnee Const. Co.</b> R.R. or street: <b>6319 Kansas Avenue</b> City, state, zip code: <b>Kansas City, KS 66111</b>				
4. Locate with "X" in section below: N W E S 1 Mile			Sketch map: 			6. Bore hole dia. <u>30</u> in. Completion date <u>7-24-78</u> Well depth <u>100</u> ft.	
5. Type and color of material			From	To	7. <input type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary		
<b>Brown clay</b>			<b>0</b>	<b>13</b>	8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input checked="" type="checkbox"/> Other		
<b>Brown medium fine sand</b>			<b>13</b>	<b>35</b>	9. Casing: Material <u>steel</u> Height: Above or below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface <u>2'</u> in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight <u>42</u> lbs./ft. Dia. <u>16</u> in. to <u>60</u> ft. depth Wall Thickness: inches or Dia. <u>  </u> in. to <u>  </u> ft. depth gage No. <u>1/4"</u>		
<b>Brown coarse sand with gravel</b>			<b>35</b>	<b>50</b>	10. Screen: Manufacturer's name <u>Johnson</u> Type <u>irrigator</u> Dia. <u>16"</u> Slot/gauze <u>010</u> Length <u>40'</u> Set between <u>70</u> ft. and <u>100</u> ft. ft. and <u>  </u> ft. Gravel pack? <input checked="" type="checkbox"/> Size range of material <u>1/4"</u>		
<b>Fine sand</b>			<b>50</b>	<b>60</b>	11. Static water level: <u>  </u> mo./day/yr. <u>  </u> ft. below land surface Date <u>  </u>		
<b>Fine medium sand</b>			<b>60</b>	<b>70</b>	12. Pumping level below land surfaces: <u>50</u> ft. after <u>10</u> hrs. pumping <u>1800</u> g.p.m. <u>  </u> ft. after <u>  </u> hrs. pumping <u>  </u> g.p.m. Estimated maximum yield <u>1800</u> g.p.m.		
<b>Coarse sand &amp; gravel</b>			<b>70</b>	<b>90</b>	13. Water sample submitted: <u>  </u> mo./day/yr. <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date <u>  </u>		
<b>Coarse sand &amp; gravel w/ cobbles</b>			<b>90</b>	<b>95</b>	14. Well head completion: <u>temp. dis head</u> <input type="checkbox"/> Pitless adapter <u>  </u> inches above grade		
<b>Brown coarse sand - gravel</b>			<b>95</b>	<b>100</b>	15. Well grouted? <u>NO</u> With: <input type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input type="checkbox"/> Concrete Depth: From <u>  </u> ft. to <u>  </u> ft.		
<b>  </b>			<b>  </b>	<b>  </b>	16. Nearest source of possible contamination: ft. <u>  </u> Direction <u>  </u> Type <u>  </u> Well disinfected upon completion? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No		
<b>  </b>			<b>  </b>	<b>  </b>	17. Pump: <input type="checkbox"/> Not installed Manufacturer's name <u>F. MORSE</u> Model number <u>MC-125</u> HP <u>75</u> Volts <u>  </u> Length of drop pipe <u>60'</u> ft. capacity <u>2500</u> g.p.m. Type: <input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other		
<b>  </b>			<b>  </b>	<b>  </b>	20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <b>Southern Wellpoint Co., Inc.</b> #235 Business name License No. Address <u>2935 N. Toledo, Tulsa OK</u> Signed <u>A.W. Macomber</u> Date <u>5/23/78</u> Authorized representative		
18. Elevation: Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input type="checkbox"/> Upland <input type="checkbox"/> Valley		19. Remarks: <b>Our contract with Shawnee states "All holes shall be filled to the satisfaction of the owner and/or engineers at no cost to our firm."</b>				20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <b>Southern Wellpoint Co., Inc.</b> #235 Business name License No. Address <u>2935 N. Toledo, Tulsa OK</u> Signed <u>A.W. Macomber</u> Date <u>5/23/78</u> Authorized representative	

Forward the white, blue and pink copies to the Department of Health and Environment

**A.W. Macomber, President**