

1 LOCATION OF WATER WELL: County: Wyandotte Fraction SE 1/4 SW 1/4 NE 1/4 Section Number 34 Township Number T 10 S Range Number R 25 E/W

Distance and direction from nearest town or city street address of well if located within city? ~120' E of Conway Trucking & 300' N of Donovan, KC

2 WATER WELL OWNER: Huhtamaki Americas Board of Agriculture, Division of Water Resources Application Number: RR#, St. Address, Box#: 9201 Packaging Drive City, State, ZIP Code: DeSoto, KS 66018

3 LOCATE WELL'S LOCATION WITH AN 'X' IN SECTION BOX: [Diagram showing a 2-mile square divided into four quadrants (NW, NE, SW, SE) with an 'X' in the NE quadrant.] 4 DEPTH OF COMPLETED WELL: 30 ft. ELEVATION: ... WELL'S STATIC WATER LEVEL: ... Pump test data: ... Est. Yield: ... Bore Hole Diameter: 8 in. to 30 ft. ... WELL WATER TO BE USED AS: 10 Monitoring well

5 TYPE OF BLANK CASING USED: 2 PVC Casing diameter: 2 in. to 10 ft. Dia. Casing height above land surface: 3 in., weight ... TYPE OF SCREEN OR PERFORATION MATERIAL: 7 PVC SCREEN OR PERFORATION OPENINGS ARE: 3 Mill slot SCREEN-PERFORATED INTERVALS: From 10 ft. to 30 ft. GRAVEL PACK INTERVALS: From 7 ft. to 30 ft.

6 GROUT MATERIAL: 3 Bentonite 4 Other Concrete Grout intervals: From 0 ft. to 1 ft. From 1 ft. to 7 ft. What is the nearest source of possible contamination: 10 Livestock pens 14 Abandoned water well 15 Oil well/Gas well Direction from well? How many feet?

Table with columns: FROM, TO, LITHOLOGIC LOG, FROM, TO, PLUGGING INTERVALS. Rows show lithology from 0-1 ft (Concrete), 1-7.5 ft (Clay, some silt, Dark Gray), 7.5-13 ft (Clay, trace silt, Dark Brown), 13-27 ft (Sand (f), some silt, Brown), 27-30 ft (Sand (f-m), some silt, Brown).

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 7/26/2007 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 527 This Water Well Record was completed on (mo/day/yr) 10/15/07 under the business name of GeoCore, Inc. by (signature) Dale Roll

INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Bureau of Water, Topeka, Kansas 66620-0001. Telephone: 913-296-5545. Send one to WATER WELL OWNER and retain one for your records.

OFFICE USE ONLY T R EW SEC 1/4 1/4 1/4 1/4