

USE TYPEWRITER OR BALL POINT PEN-PRESS FIRMLY, PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County WYANDOTTE	Fraction NW^{1/4} NW^{1/4} SE^{1/4}	Section number 27	Township number T 10	Range number R 25 E
2. Distance and direction from nearest town or city: Street address of well location if in city:				3. Owner of well: OWENS-CORNING FIBERGLAS CORPORATION R.R. or street: City, state, zip code: KANSAS CITY, KANSAS		
4. Locate with "X" in section below: N W E S 1 Mile 1 Mile		Sketch map: KINDELBERGER RD. FENCE WELL #8 FAIRFAX RD.		<input checked="" type="checkbox"/> Bore hole dia. 42 in. Completion date 7-28-78 <input checked="" type="checkbox"/> Well depth 116 ft. 7. <input type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary 8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input checked="" type="checkbox"/> Industry <input type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other 9. Casing: Material STEEL Height: Above or below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface 12 in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight _____ lbs./ft. Dia. 18 in. to 75 ft. depth Wall Thickness: inches or Dia. _____ in. to _____ ft. depth gage No. .410"		
5. Type and color of material				From	To	
ASPHALT, GRAVEL FILL				0'0"	16"	
BRN CLAYEY SILT				10'6"	6'0"	
BRN VERY FINE SAND				6'0"	17'0"	
GRAY FINE TO MED. SAND w/TR COARSE SAND				17'0"	30'0"	
GRAY MED. TO FINE w/COARSE SAND & TR. GRAVEL				30'0"	35'0"	
GRAY MED. TO COARSE SAND w/FINE SAND				35'0"	44'0"	
GRAY FINE TO MED. SAND w/TR. COARSE SAND				44'0"	49'0"	
GRAY COARSE TO MED. SAND w/TR F. SAND, GRAVEL, CLAY				49'0"	58'0"	
GRAY MED. TO FINE SAND w/COARSE SAND, SOME LIGNITE				58'0"	63'0"	
GRAY COARSE TO MED. SAND w/GRAVEL				63'0"	66'0"	
(UPPER FT.) BOULDERS, GRAY MED. TO FINE SAND				66'0"	70'0"	
GRAY MED. TO COARSE SAND w/FINE SAND				70'0"	72'0"	
GRAY COARSE TO MED. SAND w/GRAVEL & FEW BOULDERS				72'0"	81'0"	
GRAY COARSE TO MED. SAND w/GRAVEL & BOULDERS				81'0"	118'4"	
GRAY SHALE				118'4"	120'0"	
(Use a second sheet if needed)						
18. Elevation: 745 Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input type="checkbox"/> Upland <input checked="" type="checkbox"/> Valley	19. Remarks:		10. Screen: Manufacturer's name LAYNE S. STEEL Type SHUTTER Dia. 18" Slot/gauze NO. 5 Length 40' Set between 75 ft. and 115 ft. Gravel pack? <input checked="" type="checkbox"/> Size range of material BUILDERS #25 11. Static water level: _____ mo./day/yr. 20.5 ft. below land surface Date 5-7-79 12. Pumping level below land surfaces: <input checked="" type="checkbox"/> 3.5 ft. after 1 hr. pumping 1016 g.p.m. _____ ft. after _____ hrs. pumping _____ g.p.m. Estimated maximum yield 1500 g.p.m. 13. Water sample submitted: _____ mo./day/yr. <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date _____ 14. Well head completion: <input type="checkbox"/> Pitless adapter _____ Inches above grade 15. Well grouted? _____ With: <input checked="" type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input type="checkbox"/> Concrete Depth: From 0 ft. to 20 ft. 16. Nearest source of possible contamination: NONE _____ ft. _____ Direction _____ Type _____ Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No 17. Pump: <input checked="" type="checkbox"/> Not installed Manufacturer's name LAYNE Model number 74413 HP 100 Volts 440 Length of drop pipe 50 ft. capacity 900 g.p.m. Type: <input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other 20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. LAYNE - WESTERN CO. 102 Business name License No. _____ Address 1010 W. 37th ST. K.C. MO. Signed W.B. Russell Date 3-21-79 Authorized representative			

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5