

USE TYPEWRITER OR BALL POINT PEN-PRESS FIRMLY, PRINT CLEARLY.

T R EW sec 1/4 1/4 1/4 No.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas State Dept. Of Health
(Water Well Contractors)
Forbes-Bldg. 740
Topeka, Kansas 66620

1 Location of well:	County WYANDOTTE	Township name	Fraction S.W. 1/4 N.E. 1/4 SW	Section number 28	Town number 10 S.	Range number 25 SW.
Distance and direction from nearest town or city: INK. C. KS			3 Owner of well: GARNEY CONST. CO.			
Street address of well location if in city: B.P.U. - QUINDARO DISTRICT			Address: 1331 N.W. VIVION RD. K.C. MO.			
Locate with "X" in section below:		Sketch map:			4 Well depth: 83 ft. Date of completion 3/12/76 Well diameter 42 in.	
					5 <input type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary	
2 WELL No. 4		Type and color of material			6 Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Commercial <input type="checkbox"/> Test well <input checked="" type="checkbox"/> DEWATERING	
TOPSOIL					7 Casing: Material STEEL Height: above/below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface 24 in. Diam. _____ Weight 29.3 lbs./ft. _____ 12 in. to 44 ft. depth Drive shoe? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No _____ in. to _____ ft. depth	
BROWN SILTY CLAY, VERY STIFF					8 Screen: Manufacturer DOERR Type SLOTTED Dia. 12" Slot/gauze 7 GA. Length 40' Set between 44 ft. and 84 ft. _____ Fittings: Gravel pack <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No Size range of material 1/4"	
BLUE CLAY					9 Static water level: 21.5 ft. below land surface Date 3/12/76	
GRAY FINE SAND WITH CLAY BALLS					<input checked="" type="checkbox"/> Pumping level below land surfaces: 65 ft. after 720 hrs. pumping 350 g.p.m. _____ ft. after _____ hrs. pumping _____ g.p.m. Estimated maximum yield <input checked="" type="checkbox"/> _____ g.p.m.	
VERY FINE SAND WITH CLAY BALLS					11 Water sample submitted: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date _____	
FINE SAND					12 Well head completion: <input type="checkbox"/> Pitless adapter <input checked="" type="checkbox"/> Inches above grade	
WOOD					13 Well grouted? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No NATURAL BACKFILL <input type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite Depth: From 0 ft. to 83 ft.	
VERY FINE SAND					14 Nearest source of possible contamination: COAL PILE ft. 100 Direction WEST Type _____ Well disinfected upon completion? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	
MEDIUM TO COARSE SAND & GRAVEL					15 Pump: <input checked="" type="checkbox"/> Not installed Manufacturer's name _____ Model number _____ HP _____ Volts _____ Length of drop pipe _____ ft. capacity _____ g.m.p. Type: <input type="checkbox"/> Submersible <input type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other	
(use a second sheet if needed)						
16 Remarks: elevation APPROX. 800-750 <small>ft. m.</small>				17 Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. LAYNE-WESTERN Co. 149 Business name _____ License No. _____ Address 1010 W. 34TH - K.C. MO. Signed [Signature] Date 3/12/76 Authorized representative		
Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input type="checkbox"/> Upland <input checked="" type="checkbox"/> Valley						

10 SW 28 88 SUNE SW