

USE TYPEWRITER OR BALL POINT PEN-PRESS FIRMLY, PRINT CLEARLY.

WATER WELL RECORD  
KSA 82a-1201-1215

Kansas Department of Health and Environment-Division of Environment  
(Water well Contractors)  
Topeka, Kansas 66620

1. Location of well: County <b>WYANDOTTE</b>		Fraction <del>NE</del> <del>SE</del> <del>NW</del> <del>SW</del> <b>SE 1/4</b> <b>SE 1/4</b> <b>SW 1/4</b>		Section number <del>35</del> <b>35</b>	Township number <del>10 S</del> <b>10 S</b>	Range number <del>35 E</del> <b>35 E</b>
2. Distance and direction from nearest town or city: <b>IN</b>			3. Owner of well: <b>PHILLIPS PETROLEUM CO</b>			
Street address of well location if in city: <b>K.C. KANSAS</b>			R.R. or street: <b>2029 FAIRFAX</b>			
			City, state, zip code: <b>K.C., KANSAS</b>			
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. <b>5.6</b> in. Completion date <b>7-9-76</b> Well depth <b>107</b> ft.		
				7. <input checked="" type="checkbox"/> Cable tool <input checked="" type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input type="checkbox"/> Reverse rotary		
				8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input checked="" type="checkbox"/> Industry <input type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other		
				9. Casing: Material <b>STL</b> Height: Above or below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface <b>30"</b> in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight <input type="checkbox"/> lbs./ft. Dia. <b>2.6</b> in. to <b>6.7</b> ft. depth Wall Thickness: inches or Dia. <input type="checkbox"/> in. to <input type="checkbox"/> ft. depth gage No. <b>438</b>		
5. Type and color of material		From	To	10. Screen: Manufacturer's name <b>JOHN SOW</b>		
<b>Fill - cinders, concrete</b>		<b>0</b>	<b>7'6"</b>	Type <b>WW</b> Dia. <b>2.6</b>		
<b>Gray silty clay</b>		<b>7'6"</b>	<b>12'</b>	Slot/gauze <b>100</b> Length <b>40</b>		
<b>Gray fine to med. sand</b>		<b>12</b>	<b>34</b>	Set between <b>67</b> ft. and <b>107</b> ft.		
<b>Gray med. - coarse sand</b>		<b>34</b>	<b>57</b>	Gravel pack? <input checked="" type="checkbox"/> Size range of material <b>1/8" - 1/4"</b>		
<b>Gray coarse - med sand</b>		<b>57</b>	<b>105</b>	11. Static water level: <input type="checkbox"/> mo./day/yr. <b>22.1</b> ft. below land surface Date <b>4-8-76</b>		
<b>Gray shale -</b>		<b>105</b>	<b>105'</b>	12. Pumping level below land surfaces: <b>30.6</b> ft. after <b>2</b> hrs. pumping <b>2326</b> g.p.m. <input type="checkbox"/> ft. after <input type="checkbox"/> hrs. pumping <input type="checkbox"/> g.p.m. Estimated maximum yield <b>3000</b> g.p.m.		
				13. Water sample submitted: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date <input type="checkbox"/>		
				14. Well head completion: <input type="checkbox"/> Pitless adapter <b>30</b> inches above grade		
				15. Well grouted? <input checked="" type="checkbox"/> With: <input type="checkbox"/> Neat cement <input checked="" type="checkbox"/> Bentonite <input type="checkbox"/> Concrete Depth: From <b>0</b> ft. to <b>20</b> ft.		
				16. Nearest source of possible contamination: ft. <b>200</b> Direction <b>EAST</b> Type <b>RIVER</b> Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No		
				17. Pump: <input type="checkbox"/> Not installed Manufacturer's name <b>LAYNE</b> Model number <b>VHS</b> HP <b>100</b> Volts <b>460</b> Length of drop pipe <b>60</b> ft. capacity <b>1500</b> g.p.m. Type: <input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other		
18. Elevation: <b>745</b> ft		19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <b>LAYNEWESTERN</b> <b>102</b> Business name License No. Address <b>1010 W. 39; K.C.MO.</b> Signed <b>WBR</b> Date <b>7-8-76</b> Authorized representative		

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5