

35

Alma

recheck

yd R

USE TYPEWRITER OR BALL POINT PEN-PRESS FIRMLY, PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

CCA

1. Location of well: County WABAUNSEE Fraction NE 1/4 SW 1/4 SW 1/4 Section number 3 Township number T 11 R 10 Range number 10

2. Distance and direction from nearest town or city: 5 S 1/2 W 3. Owner of well: JEFF LANDERS
Street address of well location if in city: OF WAMEGO R.R. or street: 809 PINE ST.
City, state, zip code: WAMEGO, KS 66547

4. Locate with "X" in section below: Sketch map:

6. Bore hole dia. 8 in. Completion date 7-5-78
Well depth 130 ft.

7. Cable tool Rotary Driven Dug
 Hollow rod Jetted Bored Reverse rotary

8. Use: Domestic Public supply Industry
 Irrigation Air conditioning Stock
 Lawn Oil field water Other

9. Casing: Material PVC Height: 60 or below
Threaded Welded Surface 24 in.
RMP PVC 92 Weight 2.58 lbs./ft.
Dia. 5 in. to 130 ft. depth Wall Thickness: inches or
Dia. 5 in. to 130 ft. depth gage No. 274

5. Type and color of material	From	To
TOP SOIL	0	3
Limestone, shaley, yellow	3	25
Shale, grey	25	37
Limestone, yellow, loose	37	42
Shale, grey	42	59
Limestone, grey	59	68
Shale, Red, B.K.	68	90
Limestone, yellow	90	95
Shale, grey	95	130

10. Screen: Manufacturer's name PUMPEO MPE
Type PVC Dia. 5
1020 gauge Length 40
Set between 35 ft. and 55 ft.
80 ft. and 100 ft.
Gravel pack? Size range of material 20-40

11. Static water level: 35 ft. below land surface Date 7-5-78 mo./day/yr.

12. Pumping level below land surfaces:
 ft. after hrs. pumping g.p.m.
 ft. after hrs. pumping g.p.m.
Estimated maximum yield 5 g.p.m.

13. Water sample submitted: mo./day/yr.
 Yes No Date 7-5-78

14. Well head completion: CAP
 Pitless adapter 24 inches above grade

15. Well grouted?
With: Neat cement Bentonite Concrete
Depth: From 0 ft. to 10 ft.

16. Nearest source of possible contamination:
ft. 200 Direction E Type SEPTIC
Well disinfected upon completion? Yes No

17. Pump: Not installed
Manufacturer's name
Model number HP Volts
Length of drop pipe ft. capacity g.p.m.
Type:
 Submersible Turbine
 Jet Reciprocating
 Centrifugal Other

18. Elevation: 1177
Topography: Hill Slope Upland Valley

19. Remarks: OWNER TO INSTALL SLAB

20. Water well contractor's certification:
This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.
STRODER DAIG CO License No. 182
Business name RTI HOLTON, KS
Address
Signed Dale Ashm Date 7-7-78
Authorized representative

1160 PM

T 11 R 10 S 35 SW 1/4

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5