

USE TYPEWRITER OR BALL POINT PEN-PRESS FIRMLY, PRINT CLEARLY.

WATER WELL RECORD  
KSA 82a-1201-1215

Kansas Department of Health and Environment-Division of Environment  
(Water well Contractors)  
Topeka, Kansas 66620

118

DAB

1. Location of well: County Waubesa Fraction SE 1/4 NE 1/4 SE 1/4 Section number 25 Township number T 11 S Range number R 11 E

2. Distance and direction from nearest town or city: 1 3/4 mi East of Paxico, Ks Street address of well location if in city: \_\_\_\_\_

3. Owner of well: Highway Oil Co. R.R. or street: 1200 First National Bank Tower City, state, zip code: Topeka, Ks. 66103

4. Locate with "X" in section below: Sketch map: Chicago Rock Island and Pacific R.R. #3 I-70

6. Bore hole dia. 18 in. Completion date 5-1-80 Well depth 53 ft.

7.  Cable tool  Rotary  Driven  Dug  Hollow rod  Jetted  Bored  Reverse rotary

8. Use:  Domestic  Public supply  Industry  Irrigation  Air conditioning  Stock  Lawn  Oil field water  Other

9. Casing: Material Steel Height: Above or below Threading  Welded  Surface 24 in. RMP  PVC  Weight 28.6 lbs./ft. Dia. 8 in. to 8 ft. depth Wall Thickness: inches or Dia. 0 in. to 53 ft. depth gage No. 0-322

5. Type and color of material	From	To
<u>Topsoil</u>	<u>0</u>	<u>2'</u>
<u>Brown Silty Clay</u>	<u>2'</u>	<u>34'</u>
<u>Blue Silty Clay w/sand</u>	<u>34'</u>	<u>36'</u>
<u>Blue Clay</u>	<u>36'</u>	<u>38'</u>
<u>Med. to Coarse Gravel</u>	<u>38'</u>	<u>42'</u>
<u>Coarse to Med. Gravel</u>	<u>42'</u>	<u>47'</u>
<u>Shale</u>	<u>47'</u>	<u>53'</u>

10. Screen: Manufacturer's name Johnson Stainless Steel Type Wirewound Dia. 8" Slot/gauze 200 Length 7' Set between 40 ft. and 47 ft. Gravel pack? yes Size range of material 1/2" x 1/4"

11. Static water level: \_\_\_\_\_ mo./day/yr. 31.8 ft. below land surface Date 5-6-80

12. Pumping level below land surfaces: \_\_\_\_\_ ft. after 10 hrs. pumping 164 g.p.m. \_\_\_\_\_ ft. after \_\_\_\_\_ hrs. pumping \_\_\_\_\_ g.p.m. Estimated maximum yield 125 g.p.m.

13. Water sample submitted: \_\_\_\_\_ mo./day/yr.  Yes  No Date MAY 7 '80

14. Well head completion:  Pitless adapter 30 inches above grade  Well grouted? yes With:  Neat cement  Bentonite  Concrete Depth: From 18 ft. to 20 ft.

16. Nearest source of possible contamination: \_\_\_\_\_ ft. 1500 Direction West Type River Well disinfected upon completion?  Yes  No

17. Pump: \_\_\_\_\_ Not installed Manufacturer's name Jacuzzi Model number 561XLP HP 15 Volts 460 Length of drop pipe 40.5 ft. capacity 100 g.p.m. Type:  Submersible  Turbine  Jet  Reciprocating  Centrifugal  Other

(Use a second sheet if needed)

18. Elevation: 980 Topography:  Hill  Slope  Upland  Valley

19. Remarks: WELL #3

20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Layne-Weitzen 199 Business name License No. Address 1010 W 39 KCMO Signed Dan P. Hign Date 6/6/80 Authorized representative

11  
11  
W  
95  
SCALE SE  
1/4 1/4 1/4

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5