

193

WELL

WELL

USE TYPEWRITER OR BALL POINT PEN-PRESS FIRMLY, PRINT CLEARLY.

WATER WELL RECORD  
KSA 82a-1201-1215

Kansas Department of Health and Environment-Division of Environment  
(Water well Contractors)  
Topeka, Kansas 66620

1. Location of well: County SHAWNEE Fraction NE NW SE ~~1/4~~ 1/4 ~~1/4~~ Section number 3 Township number T 11 S R 13 EW

2. Distance and direction from nearest town or city: 7 S Street address of well location if in city: OF ROSSVILLE 3. Owner of well: DON RODGERS R.R. or street: City, state, zip code: ROSSVILLE, KS.

4. Locate with "X" in section below: Sketch map:

6. Bore hole dia. 10 in. Completion date 6-14-76  
Well depth 55 ft.

7.  Cable tool  Rotary  Driven  Dug  
 Hollow rod  Jetted  Bored  Reverse rotary

8. Use:  Domestic  Public supply  Industry  
 Irrigation  Air conditioning  Stock  
 Lawn  Oil field water  Other

9. Casing: Material PVC Height: Above or below  
Threaded  Welded  Surface 24 in.  
RMP PVC 3/4 Weight 2.74 lbs./ft. MNC  
Dia. 5 in. to 55 ft. depth Wall Thickness: inches or  
Dia. 5 in. to 55 ft. depth gage No. 258

5. Type and color of material	From	To
<u>TOP SOIL</u>	<u>0</u>	<u>4</u>
<u>SANDY CLAY</u>	<u>4</u>	<u>39</u>
<u>FINE SAND</u>	<u>39</u>	<u>46</u>
<u>COURSE SAND-GRAVEL</u>	<u>46</u>	<u>55</u>

10. Screen: Manufacturer's name PUMPCO  
Type PVC Dia. 5  
Slot/gauze .030 Length 8  
Set between 47 ft. and 52 ft.  
ft. and 52 ft.  
Gravel pack?  Size range of material .030-2.00

11. Static water level: 20 ft. below land surface Date 6-14-76 mo./day/yr.

12. Pumping level below land surfaces: AIR TEST  
ft. after \_\_\_\_\_ hrs. pumping \_\_\_\_\_ g.p.m.  
ft. after \_\_\_\_\_ hrs. pumping \_\_\_\_\_ g.p.m.  
Estimated maximum yield 50 g.p.m.

13. Water sample submitted: \_\_\_\_\_ mo./day/yr.  
Yes  No  Date \_\_\_\_\_

14. Well head completion: CAPIED  
 Pitless adapter 24 inches above grade

15. Well grouted?   
With:  Neat cement  Bentonite  Concrete  
Depth: From 5 ft. to 12 ft.

16. Nearest source of possible contamination:  
ft. 100 Direction E Type SEPTIC  
Well disinfected upon completion?  Yes  No

17. Pump:  Not installed  
Manufacturer's name \_\_\_\_\_ HP \_\_\_\_\_ Volts \_\_\_\_\_  
Length of drop pipe \_\_\_\_\_ ft. capacity \_\_\_\_\_ g.p.m.  
Type:  
 Submersible  Turbine  
 Jet  Reciprocating  
 Centrifugal  Other

18. Elevation: 925 Topography:  Hill  Slope  Upland  Valley

19. Remarks: OWNER WILL INSTALL SLAB

20. Water well contractor's certification:  
This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.  
STRADER DRUG CO INC 182  
Business name License No.  
Address PT 1 HOLLON KS  
Signed Dale Graham Date 6-14-76  
Authorized representative

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5