


USE TYPEWRITER OR BALL  
POINT PEN-PRESS FIRMLY,  
PRINT CLEARLY.

WATER WELL RECORD  
KSA 82a-1201-1215

Kansas Department of Health and  
Environment-Division of Environment  
(Water well Contractors)  
Topeka, Kansas 66620

NW-SW-NE

ACB

1. Location of well:		County <b>Shawnee</b>	Fraction <b>Between the E<sup>1</sup>/<sub>2</sub> of the NW<sup>1</sup>/<sub>4</sub> &amp; W<sup>1</sup>/<sub>2</sub> of the NE<sup>1</sup>/<sub>4</sub></b>	Section number <b>15</b>	Township number <b>T 11 S R 14 E W</b>	Range number <b>14</b>
2. Distance and direction from nearest town or city: <b>1 1/2 mi. east of Silver Lake, Ks.</b> Street address of well location if in city:				3. Owner of well: <b>Eugene Herring</b> R.R. or street: <b>Ozawkie, Kansas</b> City, state, zip code: <b>Meriden, Kansas 66542</b>		
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. <b>30</b> in. Completion date <b>6-5-76</b> Well depth <b>87</b> ft.		
				7. Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary		
5. Type and color of material		From	To	8. Use: Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other		
Top soil & fine sand		0	5	9. Casing: Material <b>Transite</b> Height (Above or below) <b>12</b> in. Threaded <input type="checkbox"/> Welded <input type="checkbox"/> Surface <input type="checkbox"/> RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight <input type="checkbox"/> lbs./ft. Dia. <b>16</b> in. to <b>48</b> ft. depth Wall thickness: inches or Dia. <input type="checkbox"/> in. to <input type="checkbox"/> ft. depth Case No. <b>75</b>		
Brown Clay		5	23	10. Screen: Manufacturer's name <b>Johnson Well Co.</b> Type <b>Transite</b> Dia. <input type="checkbox"/> Slot/gauze <b>1/8x8</b> Length <b>39</b> ft. Set between <b>48</b> ft. and <b>87</b> ft. Gravel pack? <input checked="" type="checkbox"/> Size range of material <b>5/8</b>		
Fine sand		23	27	11. Static water level: <b>24</b> ft. below land surface Date <b>6-5-76</b>		
Medium brown gravel		27	50	12. Pumping level below land surfaces: <b>32</b> ft. after <b>1</b> hrs. pumping <b>1000</b> g.p.m. <b>34</b> ft. after <b>2</b> hrs. pumping <b>1200</b> g.p.m. Estimated maximum yield <b>2500</b> g.p.m.		
Medium green gravel		50	53	13. Water sample submitted: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date <input type="checkbox"/>		
Gray clay		53	54	14. Well head completion: <input type="checkbox"/> Pitless adapter <input type="checkbox"/> inches above grade		
Black clay		54	55	15. Well grouted? <b>yes</b> With: <input type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input checked="" type="checkbox"/> Concrete Depth: From <b>0</b> ft. to <b>12</b> ft.		
Gray clay		55	56	16. Nearest source of possible contamination: <b>House</b> ft. <b>1700</b> Direction <b>NW</b> Type <b>House</b> Well disinfected upon completion? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No		
Gray sand		56	71	17. Pump: <input type="checkbox"/> Not installed Manufacturer's name <input type="checkbox"/> Model number <input type="checkbox"/> HP <input type="checkbox"/> Volts <input type="checkbox"/> Length of drop pipe <input type="checkbox"/> ft. capacity <input type="checkbox"/> g.p.m. Type: <input type="checkbox"/> Submersible <input type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other		
Fine gray sand		71	73	20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <b>Hobler Drilling Co. 323</b> Business name <input type="checkbox"/> License No. <input type="checkbox"/> Address <b>St. Marys, Ks. 66536</b> Signed <b>Dan Hobler</b> Date <b>6-11-76</b> Authorized representative		
Gray sand		73	75			
Small gray gravel		75	77			
Medium brown gravel		77	78			
Large brown gravel		78	87			
Stopped-gray clay		87				
18. Elevation: <b>905</b> Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input checked="" type="checkbox"/> Upland <input type="checkbox"/> Valley		19. Remarks: <b>We do not install pumps.</b>				

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5