

WATER WELL RECORD

Form WWC-5

Division of Water Resources App. No.

1 LOCATION OF WATER WELL: County: Shawnee, Fraction 1/4 NW 1/4 SW 1/4 NE 1/4, Section Number 31, Township No. T 11 S, Range Number R 16, Global Positioning System (GPS) information: Latitude: 39.054333, Longitude: 95.67775, Elevation: 932.85, Datum: WGS 84, NAD 83, NAD 27, Collection Method: GPS unit, Digital Map/Photo, Topographic Map, Land Survey, Est. Accuracy: <3 m, 3-5 m, 5-15 m, >15 m

2 WATER WELL OWNER: MRP Properties, Inc., RR#, Street Address, Box #: 5590 Havana St. Unit B, City, State, ZIP Code : Denver, CO 80239, 3 LOCATE WELL WITH AN "X" IN SECTION BOX: [Diagram showing a 2x2 grid with 'X' in the NE quadrant], 4 DEPTH OF COMPLETED WELL 22.5 ft., Depth(s) Groundwater Encountered (1) 20 ft. (2) N/A ft. (3) N/A ft., WELL'S STATIC WATER LEVEL 20.14 ft. below land surface measured on mo/day/yr. 10-7-2013, Pump test data: Well water was N/A ft. after N/A hours pumping N/A gpm, EST. YIELD N/A gpm, Well water was N/A ft. after N/A hours pumping N/A gpm, Bore Hole Diameter 8.25 in. to 22.5 ft., and N/A in. to N/A ft., WELL WATER TO BE USED AS: [] Public water supply [] Geothermal [] Injection well [] Domestic [] Feedlot [] Oil field water supply [] Dewatering [] Other (Specify below) [] Irrigation [] Industrial [] Domestic-lawn & garden [x] Monitoring well MW-2, Was a chemical/bacteriological sample submitted to Department? [] Yes [x] No, If yes, mo/day/yr sample was submitted N/A, Water well disinfected? [] Yes [x] No

5 TYPE OF CASING USED: [] Steel [x] PVC [] Other, CASING JOINTS: [] Glued [] Clamped [] Welded [x] Threaded, Casing diameter 2 in. to 12.5 ft., Diameter N/A in. to N/A ft., Diameter N/A in. to N/A ft., Casing height above land surface 0 in., Weight N/A lbs./ft., Wall thickness or gauge No. Schedule 40, TYPE OF SCREEN OR PERFORATION MATERIAL: [] Steel [] Stainless Steel [x] PVC [] Brass [] Galvanized Steel [] None used (open hole) [] Other (Specify), SCREEN OR PERFORATION OPENINGS ARE: [] Continuous slot [x] Mill slot [] Gauze wrapped [] Torch cut [] Drilled holes [] None (open hole) [] Louvered shutter [] Key punched [] Wire wrapped [] Saw cut [] Other (specify), SCREEN-PERFORATED INTERVALS: From 12.5 ft. to 22.5 ft., From N/A ft. to N/A ft., From N/A ft. to N/A ft., GRAVEL PACK INTERVALS: From 10.5 ft. to 22.5 ft., From N/A ft. to N/A ft., From N/A ft. to N/A ft.

6 GROUT MATERIAL: [] Neat cement [] Cement grout [x] Bentonite [x] Other Concrete 0-2-feet, Grout Intervals: From 2 ft. to 10.5 ft., From N/A ft. to N/A ft., From N/A ft. to N/A ft., What is the nearest source of possible contamination: [] Septic tank [] Lateral lines [] Pit privy [] Livestock pens [] Insecticide storage [] Other (specify below) [] Sewer lines [] Cesspool [] Sewage lagoon [x] Fuel storage [] Abandoned water well [] Watertight sewer lines [] Seepage pit [] Feedyard [] Fertilizer storage [] Oil well/gas well, Direction from well Southwest, Distance from well <250-feet

Table with 6 columns: FROM, TO, LITHOLOGIC LOG, FROM, TO, LITHO. LOG (cont.) or PLUGGING INTERVALS. Rows include: 0-0.5 Asphalt, 0.5-3 fill clay black no odor, 3-8 light brown clay soft high plast moist, 8-10 stiffer clay iron staining reddish staining clay med plast very stiff, 10-13 sandy clay red moist, 13-20 sand fine grained red moist, 20-21 wet sand, 21-22.5 light brown clay yellow moist high

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was [x] constructed, [] reconstructed, or [] plugged under my jurisdiction and was completed on (mo/day/year) 10-1-2013, and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 759, This Water Well Record was completed on (mo/day/year) 10-24-2013 under the business name of RAZEK Environmental, LLC by (signature) [Signature]

INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks and check the correct answers. Send one copy to Kansas Department of Health and Environment, Bureau of Water, Geology Section, 1000 SW Jackson St., Suite 420, Topeka, Kansas 66612-1367. Telephone 785-296-5524. Send one copy to WATER WELL OWNER and retain one for your records. Include fee of \$5.00 for each constructed well. Visit us at