

USE TYPEWRITER OR BALL POINT PEN-PRESS FIRMLY, PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well: County Leavenworth Fraction NE 1/4 SE 1/4 NW 1/4 Section number 24 Township number T 11 S R 20 Range number 20 (E/W)

2. Distance and direction from nearest town or city: 2 miles north & 1 mile west of Reno, Kansas
Street address of well location if in city: 2322 W. 75th Street, Kansas City, Kansas
3. Owner of well: Mr. Paul Griпка
R.R. or street: 2322 W. 75th Street
City, state, zip code: Kansas City, Kansas

4. Locate with "X" in section below: Sketch map:
N
W E
S
1 Mile

6. Bore hole dig. 0 in. Completion date 6-22-76
Well depth 100 ft.

7. Cable tool Rotary Driven Dug
 Hollow rod Jetted Bored Reverse rotary

8. Use: Domestic Public supply Industry
 Irrigation Air conditioning Stock
 Lawn Oil field water Other

9. Casing: Material PI Height: Above or below
Threaded Welded Surface 18 in.
RMP PVC Weight lbs./ft.
Dia. 0 in. to 102 ft. depth Wall Thickness: inches or
Dia. in. to ft. depth gage No. 258

5. Type and color of material	From	To
Top Soil	0	3
Clay - Yellow	3	10
Mud - Blue	10	35
Sand & Mud	35	45
Sand & Gravel	45	52
Shale - Blue	52	93
Lime - Brown	93	97
Shale	97	100
(Use a second sheet if needed)		

10. Screen: Manufacturer's name (Shelton Pipe)
Vinylplex, Inc.
Type PVC Dia.
Slot/gauze 06 1/16 Length
Set between 45 ft. and 52 ft.
 ft. and ft.
Gravel pack? Size range of material 1/4 - 1/8

11. Static water level: 20 ft. below land surface Date 6-22-76 mo./day/yr.

12. Pumping level below land surfaces:
 ft. after hrs. pumping g.p.m.
 ft. after hrs. pumping g.p.m.
Estimated maximum yield 15 g.p.m.

13. Water sample submitted: mo./day/yr.
 Yes No Date

14. Well head completion:
 Pitless adapter 18 Inches above grade

15. Well grouted? Yes
With: Neat cement Bentonite Concrete
Depth: From 3 ft. to 23 ft.

16. Nearest source of possible contamination:
ft. 200 Direction North Type Septic
Well disinfected upon completion? Yes No

17. Pump: Not installed
Manufacturer's name Jacuzzi
Model number 554B HP 1/2 Volts 220
Length of drop pipe 90 ft. capacity 10 g.p.m.
Type:
 Submersible Turbine
 Jet Reciprocating
 Centrifugal Other

18. Elevation:
Topography:
 Hill
 Slope
 Upland
 Valley

19. Remarks:

20. Water well contractor's certification:
This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.
BREUER, INC. 174
Business name Box 147 Basehor, KS. 66007 License No.
Address
Signed Date
Authorized representative