

264

USE TYPEWRITER OR BALL POINT PEN-PRESS FIRMLY, PRINT CLEARLY.

WATER WELL RECORD  
KSA 82a-1201-1215

Kansas Department of Health and Environment-Division of Environment  
(Water well Contractors)  
Topeka, Kansas 66620

1. Location of well:		County <b>Leavenworth</b>	Fraction <b>SW 1/4 SW 1/4 NE 1/4</b>	Section number <b>10 15</b>	Township number T <b>11</b> S R	Range number <b>21</b>	
2. Distance and direction from nearest town or city: <b>1/2 mile south &amp; 1/2 mile east of Tonganoxie</b>				3. Owner of well: <b>Mr. Don Collins</b> 7918 Gernech Kansas City, Kansas 66109			
4. Locate with "X" in section below:  Sketch map:				6. Bore hole dia. <b>8</b> in. Completion date <b>4-4-78</b> Well depth <b>125</b> ft.			
				7. <input checked="" type="checkbox"/> Cable tool <input checked="" type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input type="checkbox"/> Reverse rotary			
				8. Use: <input checked="" type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other			
				9. Casing: Material <b>PL</b> Height: Above or below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface <b>18</b> in. RMP <input type="checkbox"/> PVC <input checked="" type="checkbox"/> Weight <input type="checkbox"/> lbs./ft. Dia. <b>5</b> in. to <b>127</b> ft. depth Wall Thickness: inches or Dia. <input type="checkbox"/> in. to <input type="checkbox"/> ft. depth Gage No. <b>265</b>			
5. Type and color of material				From	To	10. Screen: Manufacturer's name <b>(Slotted Pipe)</b> <b>Vinylplex, Inc.</b> Type <b>PVC</b> Dia. <b>5"</b> Slot/gauze <b>.06 1/16</b> Length <b>20'</b> Set between <b>105</b> ft. and <b>125</b> ft. ft. and <input type="checkbox"/> ft. Gravel pack? <input checked="" type="checkbox"/> Size range of material <b>1/8 - 1/8</b>	
<b>Top Soil</b>				0	2	11. Static water level: <input type="checkbox"/> mo./day/yr. <b>51</b> ft. below land surface Date <b>4-4-78</b>	
<b>Sandstone</b>				2	23	12. Pumping level below land surfaces: ft. after <input type="checkbox"/> hrs. pumping <input type="checkbox"/> g.p.m. ft. after <input type="checkbox"/> hrs. pumping <input type="checkbox"/> g.p.m. Estimated maximum yield <b>36</b> g.p.m.	
<b>Sandy Shale</b>				23	43	13. Water sample submitted: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date <input type="checkbox"/>	
<b>Sandstone</b>				43	103	14. Well head completion: <input checked="" type="checkbox"/> Pitless adapter <b>18</b> inches above grade	
<b>Gray Sandstone</b>				103	125	15. Well grouted? <b>Yes</b> With: <input checked="" type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input type="checkbox"/> Concrete Depth: From <b>3</b> ft. to <b>15</b> ft.	
<i>very hard</i> <i>some iron</i> <i>no sulfur</i>						16. Nearest source of possible contamination: ft. <b>150'</b> Direction <b>South</b> Type <b>Septic</b> Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	
						17. Pump: <input checked="" type="checkbox"/> Not installed Manufacturer's name <input type="checkbox"/> Model number <input type="checkbox"/> HP <input type="checkbox"/> Volts <input type="checkbox"/> Length of drop pipe <input type="checkbox"/> ft. capacity <input type="checkbox"/> g.p.m. Type: <input type="checkbox"/> Submersible <input type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other	
(Use a second sheet if needed)						20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <b>BREUER, INC.</b> <b>174</b> Business name Address <b>Box 147, Basehor, Ks. 66007</b> License No. <b>66007</b> Signed <b>Robert D. Breuer</b> Date <b>3-6</b> Authorized representative	
18. Elevation: <b>910</b>		19. Remarks:					
Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input type="checkbox"/> Upland <input type="checkbox"/> Valley							

11-210-15  
T  
R  
W  
S  
E  
S  
U  
S  
S  
U  
E  
1/4  
1/4  
1/4

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5