

USE TYPEWRITER OR BALL POINT PEN-PRESS FIRMLY, PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and Environment-
Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:	County Leavenworth	Fraction SE 1/4 SE 1/4 NW 1/4	Section number 33	Township number 11	Range number 21
2. Distance and direction from nearest town or city: 3 mi. S of Tongonoxie, KS,		3. Owner of well: Mr. Paul McKie R.R. or street: Box 13367 City, state, zip code: Edwardsville, Kansas			
4. Locate with "X" in section below:		Sketch map: <i>h. section ... R 21 E T 11 S</i>		6. Bore hole dia. <u>8</u> in. Completion date 5-27-77 Well depth <u>160</u> ft.	
		7. <input checked="" type="checkbox"/> Cable tool <input checked="" type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input type="checkbox"/> Reverse rotary		8. Use: <input checked="" type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other	
		9. Casing: Material <u>Pl.</u> Height: Above or below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface <u>18</u> in. RMP <input type="checkbox"/> PVC <input checked="" type="checkbox"/> Weight <u> </u> lbs./ft. Dia. <u>5</u> in. to <u>162</u> ft. depth Wall Thickness: inches or Dia. <u> </u> in. to <u> </u> ft. depth gage No. <u>.265</u>		10. Screen: Manufacturer's name <u>Slotted Pipe Vinylplex, Inc.</u> Type <u>PVC</u> Dia. <u>5"</u> Slot/gauze <u>.06 1/16</u> Length <u>17'</u> Set between <u>135</u> ft. and <u>152</u> ft. <u> </u> ft. and <u> </u> ft. Gravel pack? <input checked="" type="checkbox"/> Size range of material <u>1/4 - 1/8</u>	
5. Type and color of material		From	To	11. Static water level: <u>80</u> ft. below land surface Date 5-27-77 mo./day/yr.	
Top Soil		0	3	12. Pumping level below land surfaces: <u> </u> ft. after <u> </u> hrs. pumping <u> </u> g.p.m. <u> </u> ft. after <u> </u> hrs. pumping <u> </u> g.p.m. Estimated maximum yield <u>7 1/2</u> g.p.m.	
Clay		3	20	13. Water sample submitted: <u> </u> mo./day/yr. <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date <u> </u>	
Shale		20	46	14. Well head completion: <input checked="" type="checkbox"/> Pitless adapter <u>18</u> Inches above grade	
Sandstone - Gray		46	60	15. Well grouted? <input checked="" type="checkbox"/> Yes With: <input checked="" type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input type="checkbox"/> Concrete Depth: From <u>3</u> ft. to <u>15</u> ft.	
Shale		60	102	16. Nearest source of possible contamination: <u>NONE</u> ft. <u> </u> Direction <u> </u> Type <u> </u> Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> No	
Sandstone - Gray		102	106	17. Pump: <u>Not installed</u> Manufacturer's name <u>Jacuzzi</u> Model number <u>5SLA</u> HP <u>1/2</u> Volts <u>220</u> Length of drop pipe <u>155</u> ft. capacity <u>7</u> g.p.m. Type: <input type="checkbox"/> Submersible <input type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other	
Sandy Shale		106	113	20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. BREUER, INC. 174 Business name License No. Address <u>Box 147, Basehor, Ks. 66007</u> Signed: <u>[Signature]</u> Date <u>5-27-77</u> Authorized representative	
Sandstone - Gray		113	119		
Sandy Shale		119	136		
Sandstone Gray (Water)		136	151		
Lime		151	160		
(Use a second sheet if needed)					
18. Elevation: <u>940</u> Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input type="checkbox"/> Upland <input type="checkbox"/> Valley	19. Remarks: WELL DRILLED IN MIDDLE OF PASTURE				

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5

BR. Co. = 920
▽ = 860