

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

See Tom Smith
SW SE SE Sec 28-11-21
noon any day

WATER WELL RECORD
KSA 82a-1201-1215

other wells
were drilled
about same time
ask Tom if
we get records

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620.

1. Location of well:		County Leavenworth	Fraction SE 1/4 NE 1/4 NW 1/4	Section number 33	Township number 11	Range number 21
2. Distance and direction from nearest town or city: Street address of well location if in city:				3. Owner of well: Mr. Paul McKie R.R. or street: Box 13367 City, state, zip code: Edwardsville, Kansas		
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. 8 in. Completion date 5-21-77 Well depth 160 ft.		
				7. Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hallow rod ☐ Jetted ☐ Bored ☐ Reverse rotary ☐		
				8. Use: ☒ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other		
				9. Casing: Material Pl Height: Above or below Threaded ☐ Welded ☒ Surface 13 in. RMP PVC ☒ Weight 13 lbs./ft. Dia. 5 in. to 162 ft. depth Wall Thickness: inches or Dia. 5 in. to 162 ft. depth gage No. 265		
5. Type and color of material		From	To	10. Screen: Manufacturer's name Slotted Pipe Vinylplex, Inc. Type PVC Dia. 5 in. Slot/gauze .06 1/16 Length 17 Set between 135 ft. and 132 ft. Gravel pack? ☒ Size range of material 1 - 1/8		
Top Soil		0	3	11. Static water level: 80 ft. below land surface Date		
Clay		3	20	12. Pumping level below land surfaces: ft. after hrs. pumping g.p.m. ft. after hrs. pumping g.p.m. Estimated maximum yield 7 1/2 g.p.m.		
Shale		20	46	13. Water sample submitted: Yes ☒ No ☐ Date		
Sandstone - Gray		46	60	14. Well head completion: 18 inches above grade ☒ Pitless adapter		
Shale		60	102	15. Well grouted? Yes With: ☒ Neat cement ☐ Bentonite ☐ Concrete Depth: From 3 ft. to 15 ft.		
Sandstone - Gray		102	106	16. Nearest source of possible contamination: NONE ft. Direction Type Well disinfected upon completion? Yes ☒ No ☐		
Sandy Shale		106	113	17. Pump: Not installed Manufacturer's name Jacuzzi Model number 5500 HP 1/2 g.p.m. 220 Length of drop pipe 155 ft. capacity g.p.m. Type: ☐ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other		
Sandstone - Gray		113	119	20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. BREWER, INC. 174 Business name Box 117, Basehor, Mo. 66007 Address Signed [Signature] Date 5/21/77 Authorized representative		
Sandy Shale		119	136			
Sandstone Gray (Water)		136	151			
Lime		151	160			
(Use a second sheet if needed)						
18. Elevation: 911 Topography: h ☐ Hill ☐ Slope ☐ Upland ☐ Valley		19. Remarks: WELL DRILLED IN MIDDLE OF PASTURE				

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5