

1 LOCATION OF WATER WELL: County: Wyandotte Fraction: NW 1/4 NE 1/4 NW 1/4 Section Number: 16 Township Number: T 11 S Range Number: R 23 EW

Distance and direction from nearest town or city street address of well if located within city? 122 N. Riverview, Kansas City, Kansas

2 WATER WELL OWNER: Sunflower Golf Course RR#, St. Address, Box #: 701 N. 7th Street City, State, ZIP Code: Kansas City, Kansas 66101 Board of Agriculture, Division of Water Resources Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: [Diagram showing a 2x2 grid with NW, NE, SW, SE quadrants and an 'X' in the NW quadrant.] 4 DEPTH OF COMPLETED WELL: 20 ft. ELEVATION: 1007.99. WELL'S STATIC WATER LEVEL: 12.82 ft. below land surface measured on 7/10/97. Pump test data: Well water was NA ft. after NA hours pumping. Est. Yield: NA gpm. Bore Hole Diameter: 8 in. to 20 ft. WELL WATER TO BE USED AS: 10 Monitoring well. Was a chemical/bacteriological sample submitted to Department? No. Water Well Disinfected? No.

5 TYPE OF BLANK CASING USED: 2 PVC. Blank casing diameter: 2 in. to 10 ft. Dia. Casing height above land surface: -4.56 in. weight Sch 40 lbs./ft. Wall thickness or gauge No. TYPE OF SCREEN OR PERFORATION MATERIAL: 7 PVC. SCREEN OR PERFORATION OPENINGS ARE: 3 Mill slot. SCREEN-PERFORATED INTERVALS: From 10 ft to 20 ft. GRAVEL PACK INTERVALS: From 8 ft to 20 ft.

6 GROUT MATERIAL: 2 Cement grout, 3 Bentonite. Grout Intervals: From 0 ft to 6 ft, From 6 ft to 8 ft. What is the nearest source of possible contamination: 16 Other (specify below) Former UST. Direction from well? West. How many feet? 200.

Table with columns: FROM, TO, LITHOLOGIC LOG, FROM, TO, PLUGGING INTERVALS. Rows: 0-0.5 Asphalt, 0.5-2 Clay, Dark Brown, 2-14 Clay, Red Brown, 14-20 Sand, Brown. Additional rows for MW5, Tag # 00194660, Flushmount; Project Name: Sunflower Golf Course; GeoCore # 501, KDHE # U4 105 10782.

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 7/2/97 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 527. This Water Well Record was completed on (mo/day/yr) 8/8/97 under the business name of GeoCore Services, Inc. by (signature) [Signature]

INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Bureau of Water, Topeka, Kansas 66620-0001. Telephone: 913-296-5545. Send one to WATER WELL OWNER and retain one for your records.

OFFICE USE ONLY T R EWM SEC. 1/2 1/2 1/2