

Per telephone conversation - Bo Russell

Nov 27, 1963

located on
 H.O. Connors' map
 BRT

WATER WELL RECORD

DRILLERS LOG OF WELL

FROM (FT.)	TO (FT.)	KIND OF MATERIAL, COLOR, ETC. (NOTE WATER ZONES, AMOUNT, QUALITY)
0	2	Soil
	8	Brn & Gray Clay
	17	Yellow Sdy Clay (Till)
	20	Soft Yell Sdy Clay (Till)
	52	Gray Sdy Clay (Till)
	55	Green SH
	58	Gray SH
	67	Brn & Gray SS
	72	Gray LS
	79	Gray SH
	91	Lt Gray LS
	92	Gray SH
	93	Black SH
	95	Dark Gray SH
	99	Dark Gray LS
	110	Gray SH
	111 1/2	Gray LS
	122	Gray Sdy SH
	137	Gray Shaly LS
	143	Gray SH
	145	Maroon SH
	152	Gray SH

Q,
 &
 Till



Eudora

Capl Cr.

Vilas

Plattsburg

Banner
 Spgs.

Well Owner Catholic Seminary

Address _____

Drilling Contractor Layne Western Co.

Date Drilled Nov. 1963

Method of Drilling Cable tools
 (Cable tool, rotary, reverse rotary, etc.)

Casing Schedule _____
 (Amount, Size, Setting—New, Used—Steel, Galv.—Gage or Weight)

Screen Data (if any): _____
 (Length, Diameter, Slot Size, Setting)

Measured depth to water on completed well (Static Level) is _____ ft. below _____
 (Land Surface, Top of Casing, Etc.)


TESTED YIELD: _____ gallons per _____
 (Min., Hour)

as determined by _____
 (Bailing, Test Pumping, Etc.)

DRAWDOWN: _____ ft. after _____ hrs.
 pumping at _____ gal. per minute.

REMARKS: Some water from till & from SS 58-67. Well not completed at time of telephone conversation. May drill on the Wyandotte or Iowa on this T.H.
 TD 152 Nov 27, 1963
 BR = 958
 *ARB

LOCATION OF WELL Topographic Sheet Walcott 7 1/2
 [Show location in Section Plat] Elev. 1010R



NE 1/4 NE 1/4 Sec. 5
 T. 11 S., R. 23 E.
 County Wyandotte

"To preserve water well information and to promote the conservation, protection, and development of ground-water resources."

Plotted Strip Log 0-152 ft (1190)