

1

LOCATION OF WATER WELL:

County: Wyandotte

Fraction NW 1/4 SE 1/4 SW 1/4

Section Number 13

Township Number T 11 S

Range Number R 24 EW

Distance and direction from nearest town or city street address of well if located within city?

5300 Kansas Ave. Kansas City, KS.

2

WATER WELL OWNER:

Fleming Foods

RR#, St. Address, Box # : 5300 Kansas Ave.


City, State, ZIP Code : Kansas City, KS.

Board of Agriculture, Division of Water Resources

Application Number:

3

LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:



1 Mile

W

E

S

4

DEPTH OF COMPLETED WELL

40'

ft. ELEVATION:

Depth(s) Groundwater Encountered 1. 32' ft. 2. ft. 3. ft.

WELL'S STATIC WATER LEVEL 31.86 ft. below land surface measured on mo/day/yr 3-24-97

Pump test data: Well water was ft. after hours pumping gpm

Est. Yield gpm; Well water was ft. after hours pumping gpm

Bore Hole Diameter 8 1/2" in. to 40' ft., and in. to ft.

WELL WATER TO BE USED AS:

5 Public water supply 8 Air conditioning 11 Injection well

1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below)

2 Irrigation 4 Industrial 7 Lawn and garden only 10 Monitoring well

Was a chemical/bacteriological sample submitted to Department? Yes No; If yes, mo/day/yr sample was submitted

Water Well Disinfected? Yes No

5

TYPE OF BLANK CASING USED:

1 Steel 3 RMP (SR) 5 Wrought iron 8 Concrete tile CASING JOINTS: Glued Clamped

2 PVC 4 ABS 6 Asbestos-Cement 9 Other (specify below) Welded

Blank casing diameter 2.375 in. to 25' ft., Dia in. to ft., Dia in. to ft.

Casing height above land surface Flush Mt. in., weight lbs./ft. Wall thickness or gauge No. SDR 40

TYPE OF SCREEN OR PERFORATION MATERIAL:

1 Steel 3 Stainless steel 5 Fiberglass 7 PVC 10 Asbestos-cement

2 Brass 4 Galvanized steel 6 Concrete tile 8 RMP (SR) 11 Other (specify)

12 None used (open hole)

SCREEN OR PERFORATION OPENINGS ARE:

1 Continuous slot 3 Mill slot 5 Gauzed wrapped 8 Saw cut 11 None (open hole)

2 Louvered shutter 4 Key punched 6 Wire wrapped 9 Drilled holes

10 Other (specify)

SCREEN-PERFORATED INTERVALS: From 40' ft. to 25' ft., From ft. to ft.

GRAVEL PACK INTERVALS: From 40' ft. to 23' ft., From ft. to ft.

6

GROUT MATERIAL:

1 Neat cement 2 Cement grout 3 Bentonite 4 Other

Grout Intervals: From 23' ft. to 4' ft., From 4' ft. to 0' ft., From ft. to ft.

What is the nearest source of possible contamination:

1 Septic tank 4 Lateral lines 7 Pit privy 10 Livestock pens 14 Abandoned water well

2 Sewer lines 5 Cess pool 8 Sewage lagoon 11 Fuel storage Farmer 15 Oil well/Gas well

3 Watertight sewer lines 6 Seepage pit 9 Feedyard 12 Fertilizer storage 16 Other (specify below)

13 Insecticide storage

Direction from well? Southeast

How many feet? 120'

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	1'50	Asphalt over ls.rx. gravel.			
1.50	6	Dk brn clay, moist-dry, firm, no odor.			
6	13	Lt brn sandy silt, dry, loose, no odor, slight dk colored banding.			
13	17	Lt brn-tan sand w/ trace of silt, fine grained, dry, no odor.			
17	18	Gray brn clay lens at 18', 2" thick.			
18	28	Lt. brn -tan silty sand to sand, dry, no odor, fine grained sand.			
28	35	Fine-coarse grained sand, wet at 32'6, no odor, well graded.			
35	40	Fine-coarse grained sand, wet, no odor, subrounded.			

7

CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 3-7-97 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 539 This Water Well Record was completed on (mo/day/yr) 3-25-97 under the business name of JB Environmental Drilling by (signature) James Becker

INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Bureau of Water, Topeka, Kansas 66620-0001. Telephone: 913-296-5545. Send one to WATER WELL OWNER and retain one for your records.

OFFICE USE ONLY
T
R
EW
SEC
1/4
1/4
1/4