

## WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: COUNTY: 095 STEVENS	Fraction SW 1/4 SW 1/4 NE 1/4	Section Number 09	Township Number T 35 S	Range Number R 37 W
--	----------------------------------	----------------------	---------------------------	------------------------

Distance and direction from nearest town or city street address of well if located within city?  
FROM HUGOTON; APPX 10 MILES SOUTH

2 WATER WELL OWNER: RICHARD CLAGGETT  
RR#, St. Address, Box #: RT 1 BOX 107C  
City, State, ZIP code: HUGOTON, KS 67951-  
Board of Agriculture, Division of Water Resources  
Application Number: 45,725

3 LOCATE WELL'S LOCATION WITH  
AN "X" IN SECTION BOX:

/ \				
1	---	NW	---	NE
M				
i	W		X	E
l				
e				
		SW		SE
\ /				

4 DEPTH OF COMPLETED WELL 623 ELEVATION: 0  
Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 171 ft. below land surface measured on mo/day/yr 06/18/04  
Pump test data: Well water was 376 ft. after 4 hours pumping 1600 gpm

Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 24 in. to 623 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: 02 IRRIGATION

Was a chemical/bacteriological sample submitted to department? No;  
If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED  
Blank casing diameter 16 in. to 623 ft., Dia in. to 0 ft., Dia in. to 0 ft.  
Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .250  
TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL  
SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS:	From 308 ft. to 348 ft.,	From 457 ft. to 467 ft.
	From 427 ft. to 447 ft.,	From 514 ft. to 524 ft.
GRAVEL PACK INTERVALS:	From 20 ft. to 623 ft.,	From 0 ft. to 0 ft.
	From 0 ft. to 0 ft.,	From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE  
Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.  
What is the nearest source of possible contamination: NONE OBSERVED  
Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	1	02 SILT			
1	16	07 FINE SAND 08 MEDIUM SAND 01 CLAY			
16	40	04 SANDY CLAY 05 SAND			
40	58	01 CLAY			
58	89	01 CLAY 05 SAND			
89	104	05 SAND 11 GRAVEL 01 CLAY			
104	169	04 SANDY CLAY 01 CLAY			
169	203	05 SAND 01 CLAY			
203	220	04 SANDY CLAY 05 SAND			
220	269	04 SANDY CLAY 05 SAND			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 06/15/04 and this record is true to the best of my knowledge and belief. Kansas  
Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 08/31/04  
under the business name of HENKLE DRILLING & SUPPLY by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: COUNTY: 095 STEVENS	Fraction SW 1/4 SW 1/4 NE 1/4	Section Number 09	Township Number T 35 S	Range Number R 37 W
--	----------------------------------	----------------------	---------------------------	------------------------

2 WATER WELL OWNER: RR#, St. Address, Box # : City, State, ZIP code :	RICHARD CLAGGETT RT 1 BOX 107C HUGOTON, KS 67951-	Board of Agriculture, Division of Water Resources Application Number: 45,725
---	---	---

SCREEN PERFORATED INTERVALS:	From 558 ft. to 618 ft.,	From 0 ft. to 0 ft.
	From 0 ft. to 0 ft.,	From 0 ft. to 0 ft.

FROM	TO	LITHOLOGIC LOG
269	303	04 SANDY CLAY 07 FINE SAND
303	348	07 FINE SAND 01 CLAY
348	429	04 SANDY CLAY 05 SAND
429	445	07 FINE SAND 01 CLAY
445	459	01 CLAY
459	464	01 CLAY 07 FINE SAND
464	481	04 SANDY CLAY
481	514	04 SANDY CLAY 05 SAND
514	524	07 FINE SAND 01 CLAY
524	559	04 SANDY CLAY 07 FINE SAND
559	564	07 FINE SAND 01 CLAY
564	574	04 SANDY CLAY 05 SAND
574	604	05 SAND 13 FINE GRAVEL 28 ROCK
604	618	05 SAND 11 GRAVEL 28 ROCK
618	630	01 CLAY
630	645	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 06/15/04 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 08/31/04 under the business name of HENKLE DRILLING & SUPPLY by (signature) *Bruce R. Henkle*