

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

T R EW sec 1/4 1/4 1/4 No.

Kansas State Dept. Of Health
(Water Well Contractors)
Forbes-Bldg. 740
Topeka, Kansas 66620

SW

1 Location of well:	County WYANDOTTIE	Township name DELEWARE	Fraction N.E. N.E.	Section number 22	Town number 115	Range number 25E	
Distance and direction from nearest town or city: K.C. KANSAS Street address of well location if in city: # 9 SYSTEM I ADAMS & OSAGE			3 Owner of well: CORP OF ENG. Address: K.C., MO.				
Locate with "X" in section below: N W E S 1 Mile			Sketch map: 			4 Well depth: 79 ft. Date of completion 9/24/74 Well diameter 30 in.	
2 Type and color of material			From			To	
			SANDY SILT WITH BRICK CINDERS			0	16
			SANDY SILT BROWN			16	27
			MED SAND BROWN			27	53
			CLAY GRAY			53	56
COARSE SAND GRAY			56	79			
(use a second sheet if needed)						5 6 Well depth: 79 ft. Date of completion 9/24/74 Well diameter 30 in.	
						6 Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Commercial <input type="checkbox"/> Test well <input checked="" type="checkbox"/> RELIEF	
						7 Casing: Material FBGLX Weight: above/below Threaded <input type="checkbox"/> Welded <input type="checkbox"/> Surface 12 in. Diam. 12 in. to 17 ft. depth Drive shoe? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No in. to in. ft. depth	
						8 Screen: Manufacturer FIBERGLASS RESOURCES Type SLOTTED Dia. 12" Slot/gauze 1/16" Length 30 Set between 77 ft. and 34 ft. Fittings: Gravel pack <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No Size range of material 1/2	
						9 Static water level: 28 ft. below land surface Date 7/30/75	
						10 Pumping level below land surfaces: 33 ft. after 4 hrs. pumping 650 g.p.m. ft. after hrs. pumping g.p.m. Estimated maximum yield 700 g.p.m.	
						11 Water sample submitted: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date	
						12 Well head completion: NONE <input type="checkbox"/> Pitless adapter <input type="checkbox"/> Inches above grade	
						13 Well grouted? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input type="checkbox"/> CONCRETE Depth: From 32 ft. to 14 ft.	
						14 Nearest source of possible contamination: ft. Direction Type Well disinfected upon completion? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	
						15 Pump: NONE <input type="checkbox"/> Not installed Manufacturer's name Model number HP Volts Length of drop pipe ft. capacity g.m.p. Type: <input type="checkbox"/> Submersible <input type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other	
16 Remarks: elevation 754 Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input type="checkbox"/> Upland <input checked="" type="checkbox"/> Valley						17 Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. LAYNE-WESTERN 149 Business name License No. Address 1910 W 39TH KCMO Signed C. Allen Date 11/25/75 Authorized representative	