


1 LOCATION OF WATER WELL:		Fraction	Section Number	Township Number	Range Number
County: WYANDOTTE		SW 1/4 SW 1/4 NE 1/4	14	T 11 S	R 25 E/W
Distance and direction from nearest town or city street address of well if located within city? 1600 GENESSEE, Kansas City, MO					
2 WATER WELL OWNER:		Board of Agriculture, Division of Water Resources			
RR#, St. Address, Box # : 4800 Main		Application Number:			
City, State, ZIP Code : Kansas City, MO 64112					
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL: 44.5 ft. ELEVATION: 760.5 ft.			
		Depth(s) Groundwater Encountered 1. 40.0 ft. 2. 40.0 ft. 3. 40.0 ft.			
		WELL'S STATIC WATER LEVEL 37.9 ft. below land surface measured on mo/day/yr 5/23/91			
		Pump test data: Well water was NA ft. after NA hours pumping NA gpm			
		Est. Yield NA gpm: Well water was NA ft. after NA hours pumping NA gpm			
		Bore Hole Diameter: 7.0 in. to 45.5 ft., and NA in. to NA ft.			
		WELL WATER TO BE USED AS: 5 Public water supply 8 Air conditioning 11 Injection well			
		1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below)			
		2 Irrigation 4 Industrial 7 Lawn and garden only ☒ Observation well			
		Was a chemical/bacteriological sample submitted to Department? Yes ☐ No ☒ If yes, mo/day/yr sample was submitted			
		Water Well Disinfected? Yes ☐ No ☒			
5 TYPE OF BLANK CASING USED:					
1 Steel		3 RMP (SR)		5 Wrought iron	
☒ PVC		4 ABS		6 Asbestos-Cement	
Blank casing diameter 2.0 in. to 44.5 ft. Dia.		7 Fiberglass		8 Concrete tile	
Casing height above land surface 40.0 in., weight 1.0 lbs./ft. Wall thickness or gauge No. Sch 40		9 Other (specify below)		CASING JOINTS: Glued ☐ Clamped ☐	
TYPE OF SCREEN OR PERFORATION MATERIAL:		☒ PVC		10 Asbestos-cement	
1 Steel		3 Stainless steel		11 Other (specify)	
2 Brass		4 Galvanized steel		12 None used (open hole)	
3 Fiber glass		5 Fiberglass		8 RMP (SR)	
4 Concrete tile		6 Concrete tile		9 ABS	
SCREEN OR PERFORATION OPENINGS ARE:		5 Gauzed wrapped		8 Saw cut	
1 Continuous slot		6 Wire wrapped		11 None (open hole)	
☒ Mill slot		7 Torch cut		9 Drilled holes	
2 Louvered shutter		10 Other (specify)		10 Other (specify)	
4 Key punched					
SCREEN-PERFORATED INTERVALS:		From 34.0 ft. to 44.0 ft.		From 34.0 ft. to 44.0 ft.	
		From 32.0 ft. to 45.5 ft.		From 32.0 ft. to 45.5 ft.	
GRAVEL PACK INTERVALS:		From 32.0 ft. to 45.5 ft.		From 32.0 ft. to 45.5 ft.	
		From 32.0 ft. to 45.5 ft.		From 32.0 ft. to 45.5 ft.	
6 GROUT MATERIAL					
1 Neat cement		2 Cement grout		3 Bentonite	
Grout Intervals: From Surface ft. to 30.0 ft.		From 30.0 ft. to 32.0 ft.		From 32.0 ft. to 32.0 ft.	
What is the nearest source of possible contamination:		7 Pit privy		10 Livestock pens	
1 Septic tank		4 Lateral lines		11 Fuel storage	
☒ Sewer lines		5 Cess pool		14 Abandoned water well	
3 Watertight sewer lines		6 Seepage pit		15 Oil well/Gas well	
8 Sewage lagoon		9 Feedyard		16 Other (specify below)	
13 Insecticide storage					
Direction from well? East		How many feet? 20			
FROM TO LITHOLOGIC LOG		FROM TO LITHOLOGIC LOG			
Surface 5.0 ft. Dk. Brown-Black, low plastic silty clay with sand and gravel fill		25.0 30.0 ft. Same			
5.0 10.0 ft. Stiff, light brown-black brown low plastic silty clay		30.0 40.0 ft. Dense, dark gray, fine sand with trace silt			
10.0 15.0 ft. Same		40.0 45.5 ft. Same			
15.0 20.0 ft. Same					
20.0 25.0 ft. Dense dark gray clay silt					
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was ☒ constructed, ☐ reconstructed, or ☐ plugged under my jurisdiction and was completed on (mo/day/year) 5/17/91 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 399 This Water Well Record was completed on (mo/day/yr) 6-4-91 under the business name of WOODWARD-CLYDE CONSULTANTS by (signature) Kenneth H. Woodward					
INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Bureau of Water Protection, Topeka, Kansas 66620-7320, Telephone: 913-862-9360. Send one to WATER WELL OWNER and retain one for your records.					

OFFICE USE ONLY

T

R

E/W

SEC.

1/4

1/4

1/4