

9a

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:	County WYANDOTTE	Fraction SE 1/4 SW 1/4 SE 1/4	Section number 17	Township number T 11 S	Range number R 25 E
2. Distance and direction from nearest town or city: Street address of well location if in city: 18th E KANSAS AVE KANSAS CITY, KS.			3. Owner of well: PROCTER & GAMBLE MFG. CO. R.R. or street: 18th E KANSAS AVE City, state, zip code: KANSAS CITY, KS.		
4. Locate with "X" in section below: N W SW SE S 1 Mile Sketch map: KANSAS RIVER R.R. TRACKS LYE HOUSE WELL NO. 8 KANSAS AVE.			6. Bore hole dia. 28 in. Completion date 6-9-48 Well depth 80.6 ft.		
5. Type and color of material			7. <input type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary		
Cinders			8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input checked="" type="checkbox"/> Industry <input type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other		
Sandy Clay			9. Casing: Material ALUMINO Height: Above or below Threading <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface 19 in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight <input type="checkbox"/> lbs./ft. Dia. 18 in. to 22.6 ft. depth Wall Thickness: inches or Dia. <input type="checkbox"/> in. to <input type="checkbox"/> ft. depth Gage No. <input type="checkbox"/>		
Silty Sand			10. Screen: Manufacturer's name LAYNE STAINLESS STEEL Type SHUTTER Dia. 1.2 Slot/gauze No. 1 Length 15.1 Set between 74.9 ft. and 89.9 ft. ft. and <input type="checkbox"/> ft.		
Fine Sand			Gravel pack? 19T Size range of material 18x24		
Sandy Clay			11. Static water level: <input type="checkbox"/> mo./day/yr. 39 ft. below land surface Date 6-9-48		
Mucky Sand			12. Pumping level below land surfaces: 44.3 ft. after 2 hrs. pumping 600 g.p.m. 47.0 ft. after 5 hrs. pumping 900 g.p.m. Estimated maximum yield <input type="checkbox"/> g.p.m.		
Sand & Clay Balls			13. Water sample submitted: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date <input type="checkbox"/>		
Sand & gravel (dirty)			14. Well head completion: <input type="checkbox"/> Pitless adapter 18 Inches above grade		
Coarse Sand & gravel			15. Well grouted? <input checked="" type="checkbox"/> With: <input checked="" type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input type="checkbox"/> Concrete Depth: From 0 ft. to 65 ft.		
Sand & Gravel with clay balls			16. Nearest source of possible contamination: ft. <input type="checkbox"/> Direction <input type="checkbox"/> Type <input type="checkbox"/> Well disinfected upon completion? <input type="checkbox"/> Yes <input type="checkbox"/> No		
Fine Sand			17. Pump: Manufacturer's name LAYNE Not installed Model number 18599 HP 40 Volts 220/440 Length of drop pipe 60 ft. capacity <input type="checkbox"/> g.p.m. Type: <input type="checkbox"/> Submersible <input type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input checked="" type="checkbox"/> Centrifugal <input type="checkbox"/> Other		
Sand & Gravel			20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. LAYNE - WESTERN CO. INC. Business name License No. 102 Address W.B. Russell Signed W.B. Russell Date 5/29/79 Authorized representative		
18. Elevation: 765 Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input checked="" type="checkbox"/> Upland <input type="checkbox"/> Valley			19. Remarks: Pump pulled on 5-8-79 WELL PLUGGED on 5-11-79 ① LOWER 25' FILLED CHLORINATED GRAVEL ② FOLLOWED BY 5' CONCRETE OUTSIDE OF CASING. INSIDE OF CASING FILLED TO TOP WITH CONCRETE (INNER CASING 4' BELOW GRADE) ③ 5 FEET OF CONCRETE OUTSIDE INNER CASING TOPPED WITH 14" SAND		

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5

BR < 675

726