

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County WYANDOTTE	Fraction NE 1/4 SW 1/4 SE 1/4	Section number 17	Township number T 11 S	Range number R 25 E E/W
2. Distance and direction from nearest town or city: Street address of well location if in city: K.C.K. 18th + KANSAS AVE.			3. Owner of well: PROCTER & GAMBLE MFG. CO. R.R. or street: 18th + KANSAS AVE City, state, zip code: KANSAS CITY, KS.			
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. 2 1/2 in. Completion date 1-19-77 Well depth 60 ft.		
				7. ☐ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary		
5. Type and color of material		From		To		8. Use: ☐ Domestic ☐ Public supply ☒ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other
ASPHALT		0'0"		0'6"		9. Casing: Material PVC Height: Above or below Threaded ☐ Welded ☐ Surface 12" in. RMP ☐ PVC ☒ Weight 5.4 lbs./ft. Dia. 6 in. to 34.5 ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth gage No. 432"
GRAVEL FILL		0'6"		1'6"		10. Screen: Manufacturer's name Type SLOTTED PVC Dia. 6" Slot/gauze ☐ Length 24'6" Set between 34.5 ft. and 59 ft. ft. and ☐ ft. Gravel pack? ☒ Size range of material #3 & #4
BROWN CLAYEY SILT		1'6"		12'6"		11. Static water level: ☐ mo./day/yr. 37.5 ft. below land surface Date 1-19-77
BROWN FINE TO MEDIUM SAND		12'6"		17'0"		☒ Pumping level below land surfaces: NA ☐ ft. after ☐ hrs. pumping ☐ g.p.m. ☐ ft. after ☐ hrs. pumping ☐ g.p.m. Estimated maximum yield ☐ g.p.m.
BROWN CLAYEY SANDY SILT		17'0"		33'0"		☒ Water sample submitted: ☐ mo./day/yr. ☐ Yes ☒ No Date ☐
BROWN MED TO FINE SAND W/TRACE COARSE SAND		33'0"		45'0"		14. Well head completion: ☐ Pitless adapter ☐ Inches above grade
GRAY CLAYEY SANDY SILT		45'0"		47'0"		15. Well grouted? ☒ With: ☒ Neat cement ☒ Bentonite ☐ Concrete Depth: From 0 ft. to 30 ft.
GRAY & BRN MED TO FINE SAND W/ COARSE SAND		47'0"		51'0"		☒ Nearest source of possible contamination: ft. 113 Direction N Type CHEMICAL Well disinfected upon completion? ☒ Yes ☐ No
GRAY CLAYEY SANDY SILT		51'0"		60'0"		17. Pump: ☐ Not installed Manufacturer's name JACUZZI SUB. Model number 554810 HP 1/2 Volts 230 Length of drop pipe 45 ft. capacity ☐ g.p.m. Type: ☒ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other
TOTAL DEPTH		60'0"				20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. LAYNE WESTERN 102 Business name License No. Address 1010 W. 39th K.C. MO. Signed WB Runner Date 3-21-79 Authorized representative
18. Elevation: 764		19. Remarks: WELL NO. 1-77 USED TO OBTAIN CHEMICAL AGENTS (IF ANY) RESULTING FROM A GLASS PIPELINE BREAK, ALSO USED AS A MONITORING WELL.				

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5