

WATER WELL RECORD

Form WWC-5

Division of Water Resources; App. No.

1 LOCATION OF WATER WELL: County: <u>DICKINSON</u> Distance and direction from nearest town or city street address of well if located within city? <u>SE CORNER OF UPLAND</u>		Fraction <u>NW 1/4 NW 1/4 NW 1/4</u>	Section Number <u>20</u>	Township Number <u>T 11 S</u>	Range Number <u>R 4 E</u>																																										
2 WATER WELL OWNER: <u>JUSTIN LEBERT</u> RR#, St. Address, Box # : <u>3394 RAIN RD</u> City, State, ZIP Code : <u>CHAPMAN, KS 67431</u>		Global Positioning Systems (decimal degrees, min. of 4 digits) Latitude: <u>39.08847</u> Longitude: <u>97.01854</u> Elevation: <u>1260</u> Datum: _____ Data Collection Method: _____																																													
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: <div style="text-align: center;"> </div>	4 DEPTH OF COMPLETED WELL <u>160</u> ft. Depth(s) Groundwater Encountered (1) <u>110</u> ft. (2) ft. (3) ft. WELL'S STATIC WATER LEVEL <u>91</u> ft. below land surface measured on mo/day/yr. <u>4/17/08</u> Pump test data: Well water was ft. after hours pumping gpm Est. Yield... <u>40</u> gpm: Well water was ft. after hours pumping gpm WELL WATER TO BE USED AS: 5 Public water supply 8 Air conditioning 11 Injection well 1 <u>Domestic</u> 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below) 2 Irrigation 4 Industrial 7 Domestic (lawn & garden) 10 Monitoring well Was a chemical/bacteriological sample submitted to Department? Yes No <u>X</u>; If yes, mo/day/yr Sample was submitted Water well disinfected? Yes <u>X</u> No																																														
5 TYPE OF CASING USED: 1 Steel 3 RMP (SR) 6 Asbestos-Cement 9 Other (specify below) 2 <u>PVC</u> 4 ABS 7 Fiberglass Blank casing diameter <u>6</u> in. to <u>100</u> ft., Diameter <u>6</u> in. to <u>160</u> ft., Diameter in. to ft. Casing height above land surface <u>24</u> in., Weight lbs./ft. Wall thickness or guage No. <u>SDR26</u> TYPE OF SCREEN OR PERFORATION MATERIAL: 1 Steel 3 Stainless Steel 5 Fiberglass 7 <u>PVC</u> 9 ABS 11 Other (Specify) 2 Brass 4 Galvanized Steel 6 Concrete tile 8 RM (SR) 10 Asbestos-Cement 12 None used (open hole) SCREEN OR PERFORATION OPENINGS ARE: 1 Continuous slot 3 <u>Mill slot</u> 5 Gauzed wrapped 7 Torch cut 9 Drilled holes 11 None (open hole) 2 Louvered shutter 4 Key punched 6 Wire wrapped 8 Saw cut 10 Other (specify) SCREEN-PERFORATED INTERVALS: From <u>100</u> ft. to <u>120</u> ft., From ft. to ft. GRAVEL PACK INTERVALS: From <u>25</u> ft. to <u>160</u> ft., From ft. to ft. 6 GROUT MATERIAL: 1 Neat cement 2 Cement grout 3 <u>Bentonite</u> 4 Other Grout Intervals: From <u>3</u> ft. to <u>25</u> ft., From ft. to ft., From ft. to ft. What is the nearest source of possible contamination: 1 Septic tank 4 Lateral lines 7 Pit privy 10 Livestock pens 13 Insecticide storage 16 Other (specify below) 2 <u>Sewer lines</u> 5 Cess pool 8 Sewage lagoon 11 Fuel storage 14 Abandoned water well 3 Watertight sewer lines 6 Seepage pit 9 Feedyard 12 Fertilizer storage 15 Oil well/gas well Direction from well? <u>NORTH</u> How many feet? <u>30</u>																																															
<table border="1" style="width:100%; border-collapse: collapse;"> <thead> <tr> <th>FROM</th> <th>TO</th> <th>LITHOLOGIC LOG</th> </tr> </thead> <tbody> <tr><td>0</td><td>5</td><td>CLAY</td></tr> <tr><td>5</td><td>21</td><td>SHALE, TAN</td></tr> <tr><td>21</td><td>28</td><td>LIMESTONE</td></tr> <tr><td>28</td><td>54</td><td>SHALE, TAN</td></tr> <tr><td>54</td><td>61</td><td>LIMESTONE</td></tr> <tr><td>61</td><td>96</td><td>SHALE, RED</td></tr> <tr><td>96</td><td>114</td><td>LIMESTONE H₂O</td></tr> <tr><td>114</td><td>121</td><td>SHALE, GRAY</td></tr> <tr><td>121</td><td>128</td><td>LIMESTONE</td></tr> <tr><td>128</td><td>136</td><td>SHALE, GRAY</td></tr> </tbody> </table>			FROM	TO	LITHOLOGIC LOG	0	5	CLAY	5	21	SHALE, TAN	21	28	LIMESTONE	28	54	SHALE, TAN	54	61	LIMESTONE	61	96	SHALE, RED	96	114	LIMESTONE H ₂ O	114	121	SHALE, GRAY	121	128	LIMESTONE	128	136	SHALE, GRAY	<table border="1" style="width:100%; border-collapse: collapse;"> <thead> <tr> <th>FROM</th> <th>TO</th> <th>PLUGGING INTERVALS</th> </tr> </thead> <tbody> <tr><td>136</td><td>146</td><td>LIMESTONE</td></tr> <tr><td>146</td><td>160</td><td>SHALE, GRAY</td></tr> </tbody> </table>			FROM	TO	PLUGGING INTERVALS	136	146	LIMESTONE	146	160	SHALE, GRAY
FROM	TO	LITHOLOGIC LOG																																													
0	5	CLAY																																													
5	21	SHALE, TAN																																													
21	28	LIMESTONE																																													
28	54	SHALE, TAN																																													
54	61	LIMESTONE																																													
61	96	SHALE, RED																																													
96	114	LIMESTONE H ₂ O																																													
114	121	SHALE, GRAY																																													
121	128	LIMESTONE																																													
128	136	SHALE, GRAY																																													
FROM	TO	PLUGGING INTERVALS																																													
136	146	LIMESTONE																																													
146	160	SHALE, GRAY																																													
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) <u>4/17/08</u> and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. <u>760</u> This Water Well Record was completed on (mo/day/year) <u>7/5/08</u> under the business name of <u>ASSOCIATES IN OIL & GAS INC</u> by (signature) <u>[Signature]</u>																																															
INSTRUCTIONS: Use typewriter or ball point pen. <u>PLEASE PRESS FIRMLY</u> and <u>PRINT</u> clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Bureau of Water, Geology Section, 1000 SW Jackson St., Suite 420, Topeka, Kansas 66612-1367. Telephone 785-296-5522. Send one to WATER WELL OWNER and retain one for your records. Fee of \$5.00 for each <u>constructed</u> well. Visit us at http://www.kdheks.gov/waterwell/index.html .																																															