

USE TYPEWRITER OR BALL POINT PEN-PRESS FIRMLY, PRINT CLEARLY.

T R EW sec 1/4 1/4 1/4 No.

WATER WELL RECORD KSA 82a-1201-1215
SE NW SW
NE SW SW

✓
✓

Kansas State Dept. Of Health
(Water Well Contractors)
Forbes-Bldg. 740
Topeka, Kansas 66620

1 Location of well: County **Shawnee** Township name **Tecumseh** Fraction ~~SW NW SW~~ Section number **20** Town number **T12S** Range number **R17E**

Distance and direction from nearest town or city: Street address of well location if in city: 3 Owner of well: **Henderson, Larry** Address: **Topeka, Kansas**

Locate with "X" in section below: Sketch map: N W E S 1 Mile

4 Well depth: 60 ft. Date of completion 5/12/75
Well diameter 10 in.
5 Cable tool Rotary Driven Dug
 Hollow rod Jetted Bored Reverse rotary
6 Use: Domestic Public supply Industry
 Irrigation Air conditioning Commercial
 Test well
7 Casing: Material PVC Weight: above/below
Threading Welded Surface 16 in.
Diam 5" Weight 500 lbs./ft.
 in. to ft. depth Drive shoe? Yes No
 in. to ft. depth

Type and color of material	From	To
<u>Top Soil</u>	<u>0</u>	<u>4</u>
<u>Yellow Clay</u>	<u>4</u>	<u>10</u>
<u>Yellow Clay with Sand</u>	<u>10</u>	<u>13</u>
<u>Yellow Clay with Lime Gravel</u>	<u>13</u>	<u>16</u>
<u>Yellow Lime Rock</u>	<u>16</u>	<u>17</u>
<u>Sand Stone with Lime Gravel</u>	<u>17</u>	<u>18</u>
<u>White Lime</u>	<u>18</u>	<u>22</u>
<u>Gray Shale with Lime Gravel</u>	<u>22</u>	<u>27</u>
<u>Blue Shale</u>	<u>27</u>	<u>43</u>
<u>Gray Shale</u>	<u>43</u>	<u>50</u>
<u>Blue Lime Rock</u>	<u>50</u>	<u>55</u>
<u>Blue Shale</u>	<u>55</u>	<u>60</u>
(use a second sheet if needed)		

8 Screen: Manufacturer MODERN
Type PVC Dia. 5
Slot gauge 74 Length 20
Set between 46 ft. and 60 ft.
Fittings: Gravel pack Yes No Size range of material 1/2"
9 Static water level: 6 ft. below land surface Date 5/12/75
10 Pumping level below land surfaces:
 ft. after hrs. pumping g.p.m.
 ft. after hrs. pumping g.p.m.
Estimated maximum yield 8 g.p.m.
11 Water sample submitted:
 Yes No Date
12 Well head completion:
 Pitless adapter Inches above grade
13 Well grouted? Yes No
 Neat cement Bentonite
Depth: From 3 ft. to 12 ft.
14 Nearest source of possible contamination:
ft. 90 Direction S.K. Type Septic
Well disinfected upon completion? Yes No
15 Pump: Not installed
Manufacturer's name Pumpco
Model number HP 1/3 Volt 230
Length of drop pipe 57 ft. capacity 7 g.m.p.
Type: Submersible Turbine
 Jet Reciprocating
 Certrifugal Other

16 Remarks: elevation 1070 Slab to be installed by customer
Perforations: 24 to 27 ft.
Topography: Hill Slope Upland Valley
Slopes to the North

17 Water well contractor's certification:
This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.
Cranning Drilling Co 148
Business name License No.
Address Rt. 60 Topeka
Signed Janet Cranning Date 5/20/75
Authorized representative

Forward the white, blue and pink copies to the Kansas State Dept. Of Health.

1064

BR = 1053

Form WWC-5