

1 LOCATION OF WELL: County: Leavenworth		Fraction: SW 1/4 SE 1/4 SW 1/4	Section Number: 6	Township Number: T 12S	Range Number: R 21 E E/W
Distance and direction from nearest town or city street address of well if located within city? Reno North One (1) mile					
2 WATER WELL OWNER: Kristine Leth RR#, St. Address, Box #: 11218 W 58th City, State, ZIP Code: Shawnee, KS 66203 Board of Agriculture, Division of Water Resources Application Number:					
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL: 155 ft. ELEVATION:			
		Depth(s) Groundwater Encountered 1. 110 ft. 2. 110 ft. 3. 110 ft. WELL'S STATIC WATER LEVEL 87 ft. below land surface measured on mo/day/yr 10-15-91 Pump test data: Well water was 150 ft. after 10min hours pumping 13 gpm Est. Yield 6 gpm; Well water was 150 ft. after 8 1/2 hours pumping 155 gpm Bore Hole Diameter 12 in. to 20 ft. and 8 1/2 in. to 155 ft. WELL WATER TO BE USED AS: #1 5 Public water supply 8 Air conditioning 11 Injection well * 1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below) 2 Irrigation 4 Industrial 7 Lawn and garden only 10 Monitoring well Was a chemical/bacteriological sample submitted to Department? Yes X No X ; If yes, mo/day/yr sample was submitted Water Well Disinfected? Yes X No			
5 TYPE OF BLANK CASING USED: #2 5 Wrought iron 8 Concrete tile CASING JOINTS: Glued X Clamped 1 Steel 3 RMP (SR) 6 Asbestos-Cement 9 Other (specify below) Welded 2 PVC 4 ABS 7 Fiberglass Threaded Blank casing diameter 5 in. to 155 ft. Dia. 5 in. to 155 ft. Dia. 284 in. to 265/160psi ft. Casing height above land surface 18 in. weight 284 lbs./ft. Wall thickness or gauge No. 265/160psi TYPE OF SCREEN OR PERFORATION MATERIAL X #7 * 7 PVC 10 Asbestos-cement 1 Steel 3 Stainless steel 5 Fiberglass 8 RMP (SR) 11 Other (specify) 2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS 12 None used (open hole) SCREEN OR PERFORATION OPENINGS ARE: #8 5 Gauzed wrapped * 8 Saw cut 11 None (open hole) 1 Continuous slot 3 Mill slot 6 Wire wrapped 9 Drilled holes 2 Louvered shutter 4 Key punched 7 Torch cut 10 Other (specify) SCREEN-PERFORATED INTERVALS: From 115 ft. to 155 ft. From 115 ft. to 155 ft. GRAVEL PACK INTERVALS: From 20 ft. to 155 ft. From 20 ft. to 155 ft. 6 GROUT MATERIAL: * 1 Neat cement 2 Cement grout * 3 Bentonite 4 Other Grout Intervals: From 03 ft. to 10 ft. #1 From 10 ft. to 20 ft. #2 From 20 ft. to 20 ft. #3 What is the nearest source of possible contamination: #1 10 Livestock pens 14 Abandoned water well 1 Septic tank* 4 Lateral lines 7 Pit privy 11 Fuel storage 15 Oil well/Gas well 2 Sewer lines 5 Cess pool 8 Sewage lagoon 12 Fertilizer storage 16 Other (specify below) 3 Watertight sewer lines 6 Seepage pit 9 Feedyard 13 Insecticide storage Direction from well? West How many feet? 2700					
FROM TO LITHOLOGIC LOG FROM TO PLUGGING INTERVALS					
0 04 Top Soil					
04 11 Clay					
11 16 sand					
16 18 Glacier Boulder					
18 55 Clay					
55 110 Shale					
110 155 Sandstone					
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (X) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 10-10-91 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 174 This Water Well Record was completed on (mo/day/yr) 10-15-91 under the business name of Breuer Inc. by (signature) <i>John S. Breuer</i>					
INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Bureau of Water, Topeka, Kansas 66620-0001. Telephone: 913-296-5545. Send one to WATER WELL OWNER and retain one for your records.					