

12-22-1906

# WELL INFORMATION FOR LAYNE-WESTERN CO.

This sheet is to be filled in and mailed to office upon completion of well

Sunflower Ordnance Works 10-17-42  
Name of job Date

Well No. 2 (Field) Rushton Manka  
Driller's name

1. Is there a plug in well yes

2. Thickness of plug 10 inches

Log of Well:	Formation	Formation
0' to 1'	Soil	46' to 59' Coarse sand & gravel
1' to 15'	Dry sand	to
15' to 23'	Sandy clay	to
23' to 34'	med. fine brown sand	to
34' to 46'	med. coarse sand	to
to	full of clay	to

4. Depth of well (ground level to top of plug) 58' 2" feet

5. Size and lengths of material left in well:

15 feet of 18 inch shutter screen Stamper Steel  
45 feet of 18 inch inside blank casing Steel  
15 feet of 38 inch outside blank casing Steel

6. Amount of gravel used in well 18 Ton ~~yards~~

7. Work on well began 10-9-42 Date

8. Well was completed 10-15-42 Date

9. Number of working days 6

10. Test of well:

Power used tractor  
Duration of test 1 hours  
g. p. m. pumped 650

9.2 TO 59. ft  
22.9 ft  
= 36.1 ft

From ground level { Standing water level 22' 10" feet = 22.8 ft 1190  
Pumping water level 36' 4" feet  
Drawdown 13' 6" feet

11. Pump No. \_\_\_\_\_ was installed in this well by \_\_\_\_\_

12. Remarks: Ground Surface elev = 801.94 ft Installer's Name \_\_\_\_\_

JSM

PLOTTED

(CP)