



BORING LOG

LOCATION ID: MW- 4

PROJECT: C4-046-73711 / 204.02.002

DATE: 5/ 11 /22

SITE ADDRESS:

Dry Cleaning Plus, 12101 Johnson Drive, Shawnee, KS

CLIENT:

KDHE

DRILLING CONTRACTOR:

Razek Drilling

DRILLING/SAMPLING METHOD:

HSA

LOGGED BY:

Kimberly Fitzpatrick, PE, RG

DRILLER:

Tony Poulter

DRILL RIG:

GeoProbe

BORING DIAMETER:

8"

Piezometer/Well: YES

BORING DEPTH:

19'

ELEV. (feet amsl)	DEPTH (feet bgs)	DESCRIPTION OF MATERIALS	GRAPHIC	PID READING (ppm)	RECOVERY %	SAMPLE	REMARKS
	0	6 inches asphalt					0815 began drilling PID collected via headspace in ziploc bag
	1	Dark brown, firm, medium stiffness, high plasticity, dry, fat clay (CH)		1.8			Well Completion Details: 10 foot well screen 19'-9' 6 bags sand 19'-7' 2 bags bentonite pellets 5 gallons of water flushmount surface casing
	2						
	3						
	4						
	5			2.8			
	6						
	7						
	8						
	9	Same, ~10% fine sand					
	10			1.8			

COMMENTS: continued on Sheet 2

SHEET

SHEETS

amsl = above mean sea level bgs = below ground surface

1

OF

2



BORING LOG

LOCATION ID: MW- 4

PROJECT: C4-046-73711 / 204.02.002

DATE: 5/ 11 /22

SITE ADDRESS:

Dry Cleaning Plus, 12101 Johnson Drive, Shawnee, KS

CLIENT:

KDHE

DRILLING CONTRACTOR:

Razek Drilling

DRILLING/SAMPLING METHOD:

HSA

LOGGED BY:

Kimberly Fitzpatrick, PE, RG

DRILLER:

Tony Poulter

DRILL RIG:

GeoProbe

BORING DIAMETER:

8"

Piezometer/Well: YES

BORING DEPTH:

19'

ELEV. (feet amsl)	DEPTH (feet bgs)	DESCRIPTION OF MATERIALS	GRAPHIC	PID READING (ppm)	RECOVERY %	SAMPLE	REMARKS	
	11	Same as above, Dark brown, firm, medium stiffness, high plasticity, ~5% fine sand, dry, fat clay (CH)						
	12							
	13							
	14				3.5			
	15							
	16							
	17							
	18				1.9			
	19		Refusal at 19'					
	20							

COMMENTS: continued on Sheet 3 (if applicable)

SHEET

SHEETS

amsl = above mean sea level bgs = below ground surface

2


OF

2

Dry Cleaners Plus

Approximate Monitoring Well Locations

Legend

 Feature 1

