


1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
County: JOHNSON	SE 1/4 NW 1/4 SE 1/4	3	T 12 S	R 25 (EW)

Distance and direction from nearest town or city street address of well if located within city?

2814 SHAWNEE MISSION PARKWAY, FAIRWAY, KANSAS

2 WATER WELL OWNER:	AMOCO OIL COMPANY	Board of Agriculture, Division of Water Resources
RR#, St. Address, Box # :	8700 INDIAN CREEK PARKWAY	Application Number:
City, State, ZIP Code :	OVERLAND PARK, KANSAS	

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:	4 DEPTH OF COMPLETED WELL 15.5 ft. ELEVATION:
	Depth(s) Groundwater Encountered 1. 9.5 ft. 2. ft. 3. ft.
	WELL'S STATIC WATER LEVEL 5.12 ft. below land surface measured on mo/day/yr 5-22-90
	Pump test data: Well water was ft. after hours pumping gpm
	Est. Yield gpm: Well water was ft. after hours pumping gpm
	Bore Hole Diameter 6 in. to 15.5 ft., and in. to ft.
	WELL WATER TO BE USED AS:
	1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below)
	2 Irrigation 4 Industrial 7 Lawn and garden only 10 Monitoring well
	Was a chemical/bacteriological sample submitted to Department? Yes No X If yes, mo/day/yr sample was submitted
	Water Well Disinfected? Yes No X

5 TYPE OF BLANK CASING USED:	5 Wrought iron	8 Concrete tile	CASING JOINTS: Glued Clamped
1 Steel	3 RMP (SR)	6 Asbestos-Cement	9 Other (specify below)
2 PVC	4 ABS	7 Fiberglass	10 Asbestos-cement
Blank casing diameter 2 in. to 5.0 ft., Dia			11 Other (specify)
Casing height above land surface .34 ft., weight lbs./ft. Wall thickness or gauge No. SCHED. 40			12 None used (open hole)
TYPE OF SCREEN OR PERFORATION MATERIAL:			
1 Steel	3 Stainless steel	5 Fiberglass	8 RMP (SR)
2 Brass	4 Galvanized steel	6 Concrete tile	9 ABS
SCREEN OR PERFORATION OPENINGS ARE:			
1 Continuous slot	3 Mill slot	5 Gauzed wrapped	8 Saw cut
2 Louvered shutter	4 Key punched	6 Wire wrapped	9 Drilled holes
7 Torch cut			10 Other (specify)
SCREEN-PERFORATED INTERVALS:	From 5.0 ft. to 14.0 ft., From		
	From ft. to ft., From		
GRAVEL PACK INTERVALS:	From 3.75 ft. to 15.5 ft., From		
	From ft. to ft., From		

6 GROUT MATERIAL:	1 Neat cement	2 Cement grout	3 Bentonite	4 Other
Grout Intervals:	From #2 0 ft. to 2 ft., From #3 2 ft. to 3.75 ft., From			
What is the nearest source of possible contamination:				
1 Septic tank	4 Lateral lines	7 Pit privy	10 Livestock pens	14 Abandoned water well
2 Sewer lines	5 Cess pool	8 Sewage lagoon	11 Fuel storage	15 Oil well/Gas well
3 Watertight sewer lines	6 Seepage pit	9 Feedyard	12 Fertilizer storage	16 Other (specify below)
13 Insecticide storage				
Direction from well? SOUTHWEST			How many feet? 100 ft.	

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0.0	0.2	ASPHALT			
0.2	0.5	CONCRETE			
0.5	0.8	GRAVEL			
0.8	5.5	LEAN CLAY, dark gray, brown silty with organics becoming gray green (discolored) brown			
5.5	11.5	LEAN TO FAT CLAY, reddish brown			
11.5	15.5	FAT CLAY, reddish brown			
		BOTTOM OF BORING 15.5 feet			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 5-17-90 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 416 This Water Well Record was completed on (mo/day/yr) 5-30-90 under the business name of TERRACON CONSULTANTS by (signature) <i>W. J. Semley</i>
--