


1 LOCATION OF WATER WELL: County: Johnson		Fraction NW 1/4 SW 1/4 SW 1/4		Section Number 15		Township Number T 12 S		Range Number R 25 E/W	
Distance and direction from nearest town or city street address of well if located within city? 6901 Mission Road, Prairie Village									
2 WATER WELL OWNER: Amoco Oil Company RR#, St. Address, Box # : 8700 Indian Creek Parkway, Suite 210 City, State, ZIP Code : Overland Park, KS 66210 Board of Agriculture, Division of Water Resources Application Number:									
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 			4 DEPTH OF COMPLETED WELL: 14 ft. ELEVATION: Depth(s) Groundwater Encountered 1. 8 ft. 2. ft. 3. ft. WELL'S STATIC WATER LEVEL 7.13 ft. below land surface measured on mo/day/yr 2/20/92 Pump test data: Well water was ft. after hours pumping gpm Est. Yield gpm: Well water was ft. after hours pumping gpm Bore Hole Diameter 8 in. to 14.5 ft. and in. to ft. WELL WATER TO BE USED AS: 1 Domestic 3 Feedlot 5 Public water supply 8 Air conditioning 11 Injection well 2 Irrigation 4 Industrial 6 Oil field water supply 9 Dewatering 12 Other (Specify below) <u>10 Monitoring well</u> Was a chemical/bacteriological sample submitted to Department? Yes No <u>X</u> ; If yes, mo/day/yr sample was submitted Water Well Disinfected? Yes No <u>X</u>						
5 TYPE OF BLANK CASING USED: 1 Steel 3 RMP (SR) 5 Wrought iron 8 Concrete tile CASING JOINTS: Glued Clamped <u>2 PVC</u> 4 ABS 6 Asbestos-Cement 9 Other (specify below) Welded Blank casing diameter 2 in. to 4 ft., Dia. in. to ft., Dia. in. to ft. Casing height above land surface 0 in., weight lbs./ft. Wall thickness or gauge No. Sch-40 TYPE OF SCREEN OR PERFORATION MATERIAL: 1 Steel 3 Stainless steel 5 Fiberglass 8 RMP (SR) 10 Asbestos-cement 2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS 11 Other (specify) 12 None used (open hole) SCREEN OR PERFORATION OPENINGS ARE: 1 Continuous slot 3 <u>Mill slot</u> 5 Gauzed wrapped 8 Saw cut 11 None (open hole) 2 Louvered shutter 4 Key punched 6 Wire wrapped 9 Drilled holes 7 Torch cut 10 Other (specify) SCREEN-PERFORATED INTERVALS: From 4 ft. to 14 ft., From ft. to ft. GRAVEL PACK INTERVALS: From 2 ft. to 14.5 ft., From ft. to ft. From ft. to ft., From ft. to ft.									
6 GROUT MATERIAL: 1 Neat cement 2 <u>Cement grout</u> 3 <u>Bentonite</u> 4 Other Grout Intervals: From 0 ft. to 1 ft., From 1 ft. to 2 ft., From ft. to ft. What is the nearest source of possible contamination: 1 Septic tank 4 Lateral lines 7 Pit privy 10 Livestock pens 14 Abandoned water well 2 Sewer lines 5 Cess pool 8 Sewage lagoon 11 <u>Fuel storage</u> 15 Oil well/Gas well 3 Watertight sewer lines 6 Seepage pit 9 Feedyard 12 Fertilizer storage 16 Other (specify below) 13 Insecticide storage Direction from well? South How many feet? 50									
FROM TO LITHOLOGIC LOG					FROM TO PLUGGING INTERVALS				
0 0.5 Concrete									
0.5 2.5 Olive grey soft moist clayey silt									
2.5 5 Dark grey soft, moist clayey silt									
5 9 Dark grey clayey silt with root fragments									
9 10 Mottled orange and grey clayey silt with some gravel									
10 15.75 Mottled orange and grey clayey silt with gravel									
13.75 14 Orange-grey soft, wet clayey silt									
14 14.5 Grey and orange-grey weathered shale and shale									
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 9/18/90 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. This Water Well Record was completed on (mo/day/yr) 3/3/92 under the business name of Geraghty & Miller, Inc. by (signature) <i>L. Lloyd</i>									