

1 LOCATION OF WATER WELL:		Fraction	Section Number	Township Number	Range Number
County: JOHNSON		SW 1/4 NW 1/4 NE 1/4	22	T 12 S	R 25 W
Distance and direction from nearest town or city street address of well if located within city? VILLAGE AMOCO, 3515 W 75th, PRAIRIE VILLAGE, KS 66208					
2 WATER WELL OWNER: LAW ENVIRONMENTAL INC		Board of Agriculture, Division of Water Resources			
RR#, St. Address, Box #: 10220 N. EXECUTIVE HILLS BLVD., SUITE 400		Application Number:			
City, State, ZIP Code: KANSAS CITY, MO 64153					
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL: 32 ft. ELEVATION:			
		Depth(s) Groundwater Encountered 1. 10 ft. 2. ft. 3. ft.			
		WELL'S STATIC WATER LEVEL 8 ft. below land surface measured on mo/day/yr 1/19/91			
		Pump test data: Well water was ft. after hours pumping gpm			
		Est. Yield gpm: Well water was ft. after hours pumping gpm			
		Bore Hole Diameter 10 in. to 22 ft., and 4 in. to 32 ft.			
		WELL WATER TO BE USED AS:			
		5 Public water supply 8 Air conditioning 11 Injection well 1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below) 2 Irrigation 4 Industrial 7 Lawn and garden only 10 Monitoring well			
		Was a chemical/bacteriological sample submitted to Department? Yes No X ; If yes, mo/day/yr sample was submitted			
		Water Well Disinfected? Yes No X			
5 TYPE OF BLANK CASING USED:		CASING JOINTS: Glued Clamped			
1 Steel 3 RMP (SR) 6 Asbestos-Cement 9 Other (specify below) 2 PVC 4 ABS 7 Fiberglass Threaded					
Blank casing diameter 4 in. to 22 ft. Dia 2 in. to 27 ft. Dia					
Casing height above land surface 0 in., weight lbs./ft. Wall thickness or gauge No. SCH. 40					
TYPE OF SCREEN OR PERFORATION MATERIAL:		7 PVC 10 Asbestos-cement			
1 Steel 3 Stainless steel 5 Fiberglass 8 RMP (SR) 11 Other (specify) 2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS 12 None used (open hole)					
SCREEN OR PERFORATION OPENINGS ARE:		8 Saw cut 11 None (open hole)			
1 Continuous slot 3 Mill slot 0.010" 6 Wire wrapped 9 Drilled holes 2 Louvered shutter 4 Key punched 7 Torch cut 10 Other (specify)					
SCREEN-PERFORATED INTERVALS: From 27 ft. to 32 ft.					
GRAVEL PACK INTERVALS: From 25 ft. to 32 ft.					
6 GROUT MATERIAL:		4 Other			
1 Neat cement 2 Cement grout 3 Bentonite					
Grout Intervals: From 0 ft. to 22 ft., From 2 ft. to 25 ft.					
What is the nearest source of possible contamination:		10 Livestock pens 14 Abandoned water well			
1 Septic tank 4 Lateral lines 7 Pit privy 11 Fuel storage UST 15 Oil well/Gas well 2 Sewer lines 5 Cess pool 8 Sewage lagoon 12 Fertilizer storage 16 Other (specify below) 3 Watertight sewer lines 6 Seepage pit 9 Feedyard 13 Insecticide storage					
Direction from well? S		How many feet? 35			
FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	1	CONCRETE			
1	3	BACKFILL			
3	21	SILTY CLAY, 45% SAND (FINE)			
21	22	LIMESTONE, WEATHERED			
22	26	LIMESTONE, OOLITIC, MOTTLED DENSE (FARLEY LS)			
26	32	SHALE - GRAY/GREEN (ISLAND CREEK SH MBR)			
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 1/19/91 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 530 This Water Well Record was completed on (mo/day/yr) 1/27/91 under the business name of SHAMROCK ENVIRON. DRILLING INC by (signature) Clay P. Alyen					