

1) LOCATION OF WATER WELL:		Fraction	Section Number	Township Number	Range Number
County: Johnson		NW ¼ SW ¼ NE ¼	30	T 12 S	R 25 EW
Distance and direction from nearest town or city street address of well if located within city? Located at 8130 Santa Fe, Overland Park ow-1					
2) WATER WELL OWNER: Texaco Refining and Marketing, Inc.					
RR#, St. Address, Box #: 1437 South Boulder City, State, ZIP Code: Tulsa, OK 74119 Board of Agriculture, Division of Water Resources Application Number:					
3) LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4) DEPTH OF COMPLETED WELL: 17.0 ft. ELEVATION: 1077			
A 2x2 grid representing a section box. The top-left quadrant is labeled 'NW', top-right 'NE', bottom-left 'SW', and bottom-right 'SE'. An 'X' is drawn in the center where all four quadrants meet.		Depth(s) Groundwater Encountered 1. 5.0 ft. 2. . ft. 3. . ft. WELL'S STATIC WATER LEVEL NA ft. below land surface measured on mo/day/yr NA Pump test data: Well water was NA ft. after hours pumping gpm Est. Yield NA gpm; Well water was ft. after hours pumping gpm Bore Hole Diameter 8 in. to 17.5 ft., and in. to ft. WELL WATER TO BE USED AS: 1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering ⑫ Other (Specify below) 2 Irrigation 4 Industrial 7 Lawn and garden only 10 Monitoring well Vapor Extraction Was a chemical/bacteriological sample submitted to Department? Yes No X If yes, mo/day/yr sample was submitted mitted Water Well Disinfected? Yes No			
5) TYPE OF BLANK CASING USED: 1 Steel 3 RMP (SR) 5 Wrought iron 8 Concrete tile CASING JOINTS: Glued Clamped ② PVC 4 ABS 6 Asbestos-Cement 9 Other (specify below) Welded Blank casing diameter 2 in. to 2 ft., Dia. in. to ft., Dia. in. to ft. Threaded. X Casing height above land surface - 3.0 in., weight NA lbs./ft. Wall thickness or gauge No. Sch 40 TYPE OF SCREEN OR PERFORATION MATERIAL: ⑦ PVC 10 Asbestos-cement 1 Steel 3 Stainless steel 5 Fiberglass 8 RMP (SR) 11 Other (specify) 2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS 12 None used (open hole) SCREEN OR PERFORATION OPENINGS ARE: 1 Continuous slot 3 Mill slot 5 Gauzed wrapped ⑧ Saw cut 11 None (open hole) 2 Louvered shutter 4 Key punched 6 Wire wrapped 9 Drilled holes 7 Torch cut 10 Other (specify) SCREEN-PERFORATED INTERVALS: From 2.0 ft. to 17.0 ft., From ft. to ft. Sand GRAVEL PACK INTERVALS: From 2.0 ft. to 17.0 ft., From ft. to ft. From ft. to ft., From ft. to ft.					
6) GROUT MATERIAL: 1 Neat cement 2 Cement grout ③ Bentonite 4 Other Grout Intervals: From 0.75 ft. to 2.0 ft., From ft. to ft., From ft. to ft. What is the nearest source of possible contamination: 1 Septic tank 4 Lateral lines 7 Pit privy 10 Livestock pens 14 Abandoned water well 2 Sewer lines 5 Cess pool 8 Sewage lagoon 11 Fuel storage 15 Oil well/Gas well 3 Watertight sewer lines 6 Seepage pit 9 Feedyard 12 Fertilizer storage ⑯ Other (specify below) Hydrocarbon-impacted soil Direction from well? Surrounding well How many feet? 0.0 FROM TO LITHOLOGIC LOG FROM TO PLUGGING INTERVALS 0 3 ft Black fine sandy clay 0.75 ft 2 ft Bentonite pellets 3 ft 8 ft Grayish-green fine sandy clay 8 ft 17.5 ft Reddish-brown fine sandy clay Casing height/grout variance granted by KDHE.					
7) CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was ① constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 03/21/91 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 102 This Water Well Record was completed on (mo/day/yr) 05/10/91 under the business name of LATINE-WESTERN CO. by (signature) Paul W. [Signature]					
INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Bureau of Water, Topeka, Kansas 66620-7320. Telephone: 913-296-5545. Send one to WATER WELL OWNER and retain one for your records.					