

CORRECTION(S) TO WATER WELL RECORD (WWC-5)

(to rectify lacking or incorrect information)

Location listed as:


Section-Township-Range: 30-125-25EFraction ($\frac{1}{4}$ $\frac{1}{4}$ $\frac{1}{4}$): SE SE SEOther changes: Initial statements: Wyandotte CountyCounty: Johnson

Location changed to:

30-125-25ESW SW NEChanged to: Johnson County

Comments:

verification method: Well address, city street map, legal description,
and Lenexa 1:24,000 topo. map.initials: ORL date: 10/7/2005submitted by: Kansas Geological Survey, Data Resources Library, 1930 Constant Ave., Lawrence, KS 66047-3726
to: Kansas Dept of Health & Environment, Bureau of Water, 1000 SW Jackson, Suite 420, Topeka, KS 66612-1367.

1 LOCATION OF WATER WELL:		Fraction	Section Number	Township Number	Range Number
County: WYANDOTTE		SE 1/4 SE 1/4 SE 1/4	30	T 12 S	R 25 EW
Distance and direction from nearest town or city street address of well if located within city? 8205 SANTA FE DR, OVERLAND PARK, KS					
2 WATER WELL OWNER:		Board of Agriculture, Division of Water Resources			
RR#, St. Address, Box #:		Application Number:			
City, State, ZIP Code:					
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL: 12.5 ft. ELEVATION:			
		Depth(s) Groundwater Encountered 1 ft. 2. ft. 3. ft.			
		WELL'S STATIC WATER LEVEL 12.4 ft. below land surface measured on mo/day/yr 4-10-95			
		Pump test data: Well water was ft. after hours pumping gpm			
		Est. Yield gpm: Well water was ft. after hours pumping gpm			
		Bore Hole Diameter 8.25 in. to 12.5 ft. and in. to ft.			
		WELL WATER TO BE USED AS: 5 Public water supply 8 Air conditioning 11 Injection well			
		1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below)			
		2 Irrigation 4 Industrial 7 Lawn and garden only ☒ Monitoring well			
		Was a chemical/bacteriological sample submitted to Department? Yes No ☒ If yes, mo/day/yr sample was submitted			
		Water Well Disinfected? Yes No ☒			
5 TYPE OF BLANK CASING USED:		CASING JOINTS: Glued Clamped			
1 Steel 3 RMP (SR) 5 Wrought iron 8 Concrete tile		Welded			
☒ PVC 4 ABS 7 Fiberglass		Threaded ☒			
Blank casing diameter 2 in. to 7.0 ft. Dia in. to ft. Dia in. to ft.					
Casing height above land surface -1.0 in., weight lbs./ft. Wall thickness or gauge No. SCHEDULE 40					
TYPE OF SCREEN OR PERFORATION MATERIAL:		☒ PVC 10 Asbestos-cement			
1 Steel 3 Stainless steel 5 Fiberglass 8 RMP (SR) 11 Other (specify)					
2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS 12 None used (open hole)					
SCREEN OR PERFORATION OPENINGS ARE:		8 Saw cut 11 None (open hole)			
1 Continuous slot ☒ Mill slot 0.010" 6 Wire wrapped 9 Drilled holes					
2 Louvered shutter 4 Key punched 7 Torch cut 10 Other (specify)					
SCREEN-PERFORATED INTERVALS: From 7.0 ft. to 12.5 ft. From ft. to ft. From ft. to ft.					
GRAVEL PACK INTERVALS: From 6.1 ft. to 12.5 ft. From ft. to ft. From ft. to ft.					
6 GROUT MATERIAL: 1 Neat cement 2 Cement grout ☒ Bentonite ☒ Other CONCRETE 0.0 - 1.0					
Grout Intervals: From 1.0 ft. to 6.1 ft. From ft. to ft. From ft. to ft.					
What is the nearest source of possible contamination:		10 Livestock pens 14 Abandoned water well			
1 Septic tank 4 Lateral lines 7 Pit privy ☒ Fuel storage 15 Oil well/Gas well					
2 Sewer lines 5 Cess pool 8 Sewage lagoon 12 Fertilizer storage 16 Other (specify below)					
3 Watertight sewer lines 6 Seepage pit 9 Feedyard 13 Insecticide storage					
Direction from well?		How many feet? 10			
FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0.0	0.4	CONCRETE			
0.4	0.5	GRAVEL BASE			
0.5	6.0	BLK CLAY			
6.0	11.0	GRN CLAY			
11.0	12.5	BRN-GRN CLAY			
12.5		LS			
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was ☒ constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 4-10-95 and this record is true to the best of my knowledge and belief. Kansas					
Water Well Contractor's License No. 416 This Water Well Record was completed on (mo/day/yr) 5-8-95					
under the business name of TERRACON CONSULTANTS INC by (signature) <i>Thomas J. White</i>					