

Division of Water Resources App. No.

KSA 82a-1212

Check: ☒ White Copy, ☐ Blue Copy, ☐ Pink Copy

					LOG OF BORING NO: MW-3R		SHEET NUMBER 1 OF 1	
PROJECT NAME: Amoco #8855					DRILLING/PROBING CONTRACTOR: Razek Environmental		Water Level Data Date Time Depth 8/31/2010 0842 3.86	
PROJECT LOCATION: 7446 Metcalf Ave					DRILLING METHOD / BORE DIAMETER: Hollow Stem Auger 8.25"/4.25"			
Overland Park, KS					SAMPLING METHOD: Macro Core			
PROJECT NUMBER: 17102305					TOTAL DEPTH (feet): 15		Survey Data Ground Surface: 952.88 Top Of Casing: 953.16 Ground Water:	
GEOLOGIST: M. Watson					START DATE: 8/17/2010		NOTES:	
DRILLER: Tony Poultier					COMPLETION DATE: 8/17/2010			
SAMPLE DEPTH AND TIME	PID (PPMV)	RECOVERY (FEET)	DEPTH (FEET)	WELL CONSTRUCTION		GEOLOGIC DESCRIPTION (NAME, color, particle size, characteristics)		
1150	1.3	4/5	1	Concrete Bentonite Chip Seal 2" Diameter Sch 40 Screen	Grass Surface CL: brown CLAY, damp, non-plastic, medium stiff wet	0-1 ft interval sampled for headspace only, no odor 2-3 ft interval sampled for headspace only, no odor Saturated ↓		
			2					
			3					
			4					
			5					
1155		5/5	6	10-20 Sand Filter Pack 2" Diameter Sch 40 Screen	CL: grey CLAY, wet, TR plastic, medium stiff CH: tan CLAY, wet, plastic, soft			
			7					
			8					
			9					
			10					
1200		NR	11	10-20 Sand Filter Pack 2" Diameter Sch 40 Screen	No Recovery	Not sampled below anticipated ground water level		
			12					
			13					
			14					
			15					
1215			16		Total Depth = 15 feet per KDHE			
			17					
			18					
			19					
			20					
			21					
			22					
			23					
			24					
			25					

LEGEND:

SS - Split Spoon
PID - Photoionization Detector
NR - No Recovery

Concrete

Flush Mount Vault

Grout

Bentonite Chip Seal

Filter Pack

Well Screen

ST - Shelby Tube
HSA - Hollow Stem Augers
PPMV - Parts Per Million by Volume