



Division of Water Resources App. No.

KSA 82a-1212

Check: ☒ White Copy, ☐ Blue Copy, ☐ Pink Copy

					LOG OF BORING NO: MW-5R		SHEET NUMBER 1 OF 1	
PROJECT NAME: Amoco #8855					DRILLING/PROBING CONTRACTOR: Razek Environmental		Water Level Data Date Time Depth 8/31/2010 0921 4.71	
PROJECT LOCATION: 7446 Metcalf Ave					DRILLING METHOD / BORE DIAMETER: Hollow Stem Auger 8.25"/4.25"			
Overland Park, KS					SAMPLING METHOD: Macro Core			
PROJECT NUMBER: 17102305					TOTAL DEPTH (feet): 15		Survey Data Ground Surface:	
GEOLOGIST: M. Watson					START DATE: 8/17/2010		Top Of Casing:	
DRILLER: Tony Poulter					COMPLETION DATE: 8/17/2010		Ground Water:	
SAMPLE DEPTH AND TIME	PID (PPMV)	RECOVERY (FEET)	DEPTH (FEET)	WELL CONSTRUCTION		GEOLOGIC DESCRIPTION (NAME, color, particle size, characteristics)		NOTES:
1615	0.0		1	 Bentonite Chip Seal  2" Diameter Sch 40 Screen	Grass Surface		0-1 ft interval sampled for headspace only, no odor	
	0.0	2.5/5	2		CL: brown CLAY, damp, non-plastic, medium stiff			
			3				2-3 ft interval sampled for headspace only, no odor	
			4					
			5		CL: grey CLAY, wet, TR plastic, soft		Saturated ↓	
1620		5/5	6	 10-20 Sand Filter Pack  2" Diameter Sch 40 Screen				
			7					
			8					
			9					
			10					
1625		NR	11	 10-20 Sand Filter Pack  2" Diameter Sch 40 Screen	No Recovery		Not sampled below anticipated ground water level	
			12					
			13					
			14					
			15					
1700			16		Total Depth = 15 feet per KDHE			
			17					
			18					
			19					
			20					
			21					
			22					
			23					
			24					
			25					

LEGEND:
SS - Split Spoon
PID - Photoionization Detector
NR - No Recovery

 - Concrete
 - Flush Mount Vault
 - Grout

 - Bentonite Chip Seal
 - Filter Pack
 - Well Screen

ST - Shelby Tube
HSA - Hollow Stem Augers
PPMV - Parts Per Million by Volume