

1 LOCATION OF WATER WELL:		Fraction	Section Number	Township Number	Range Number
County: <u>Johnson</u>		<u>SW</u> 1/4 <u>NW</u> 1/4 <u>NE</u> 1/4	<u>5</u>	T <u>12</u> S	R <u>25</u> <u>EW</u>
Distance and direction from nearest town or city street address of well if located within city? <u>4775 Lamar, Mission, Ks.</u>					
2 WATER WELL OWNER:		City of Mission			
RR#, St. Address, Box # :		6090 Woodson			
City, State, ZIP Code :		Mission, KS.			
		Board of Agriculture, Division of Water Resources			
		Application Number:			
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL <u>15'</u> ft. ELEVATION:			
		Depth(s) Groundwater Encountered <u>1</u> <u>6'</u> ft. 2. ft. 3. ft.			
		WELL'S STATIC WATER LEVEL <u>3'7"</u> ft. below land surface measured on mo/day/yr <u>3-18-95</u>			
		Pump test data: Well water was ft. after hours pumping gpm			
		Est. Yield gpm: Well water was ft. after hours pumping gpm			
		Bore Hole Diameter <u>8 1/2"</u> in. to <u>15'</u> ft., and in. to ft.			
		WELL WATER TO BE USED AS:			
		5 Public water supply 8 Air conditioning 11 Injection well			
		1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below)			
		2 Irrigation 4 Industrial 7 Lawn and garden only 10 Monitoring well			
		Was a chemical/bacteriological sample submitted to Department? Yes No <u>X</u> If yes, mo/day/yr sample was submitted			
		Water Well Disinfected? Yes No <u>(No)</u>			
5 TYPE OF BLANK CASING USED:		CASING JOINTS: Glued Clamped			
1 Steel 3 RMP (SR)		Welded <u>X</u>			
<u>2 PVC</u> 4 ABS		Threaded <u>SDR 13</u>			
Blank casing diameter <u>2 3/4"</u> in. to <u>5'</u> ft., Dia in. to ft., Dia in. to ft.		SCH <u>40</u>			
Casing height above land surface <u>Flush Mount</u> ft., weight lbs./ft. Wall thickness or gauge No.					
TYPE OF SCREEN OR PERFORATION MATERIAL:		7 PVC 10 Asbestos-cement			
1 Steel 3 Stainless steel 5 Fiberglass 8 RMP (SR) 11 Other (specify)					
2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS 12 None used (open hole)					
SCREEN OR PERFORATION OPENINGS ARE:		5 Gauzed wrapped 8 Saw cut 11 None (open hole)			
1 Continuous slot <u>3 Mill slot</u> 6 Wire wrapped 9 Drilled holes					
2 Louvered shutter 4 Key punched 7 Torch cut 10 Other (specify)					
SCREEN-PERFORATED INTERVALS:		From <u>15'</u> ft. to <u>5'</u> ft. From ft. to ft.			
GRAVEL PACK INTERVALS:		From <u>15'</u> ft. to <u>4'</u> ft. From ft. to ft.			
From ft. to ft. From ft. to ft.					
6 GROUT MATERIAL:		1 Neat cement 2 Cement grout 3 Bentonite 4 Other			
Grout Intervals: From <u>4'</u> ft. to <u>3'</u> ft. From <u>3'</u> ft. to <u>0'</u> ft. From ft. to ft.					
What is the nearest source of possible contamination:		10 Livestock pens 14 Abandoned water well			
1 Septic tank 4 Lateral lines 7 Pit privy <u>11 Fuel storage</u> <u>Farm</u> 15 Oil well/Gas well					
2 Sewer lines 5 Cess pool 8 Sewage lagoon 12 Fertilizer storage 16 Other (specify below)					
3 Watertight sewer lines 6 Seepage pit 9 Feedyard 13 Insecticide storage					
Direction from well? <u>West</u>		How many feet? <u>15'</u>			
FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	1.50	Brn gravelly clay, moist to wet, earthy odor, iron oxides.			
1.50	8	med yellow brn clay w/ iron oxides, moist, no odor, weathered shales w/ few weathered ls.rx. frag. Moist to wet at 6'.			
8	8.25	Ls. rx. shelf.			
8.25	15'	Brn-olive dry shale, firm, dry, no odor w/ yellowish brn sandstone stringers.			
		Gray shale, dry w/ intermittent thinning bed ls. rx. stringers, no odor.			
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) <u>constructed</u> (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) <u>3-10-95</u> and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. <u>539</u> This Water Well Record was completed on (mo/day/yr) <u>3-26-95</u> under the business name of <u>JB Environmental Drilling</u> by (signature) <u>James Becker</u>					