

WATER WELL RECORD

Form WWC-5


Division of Water Resources; App. No.

1 LOCATION OF WATER WELL: Fraction SW 1/4 NW 1/4 SW 1/4 Section Number 18 Township Number T 13 S Range Number R 1 E

Distance and direction from nearest town or city street address of well if located within city? 101 E 4th St., Solomon KS Global Positioning System (decimal degrees, min. of 4 digits)

2 WATER WELL OWNER: KDHE RR#, St. Address, Box #: 1000 SW Jackson Blvd City, State, ZIP Code: Topeka KS 66612

3 LOCATE WELL'S LOCATION WITH AN 'X' IN SECTION BOX: MW5



4 DEPTH OF COMPLETED WELL 33.85 ft. Depth(s) Groundwater Encountered 1 ft. 2 ft. 3 ft. WELL'S STATIC WATER LEVEL 24.50 ft. below land surface measured on mo/day/yr 4/15/14

5 TYPE OF CASING USED: 1 Steel 2 PVC 3 RMP (SR) 4 ABS 5 Wrought Iron 6 Asbestos-Cement 7 Fiberglass 8 Concrete tile 9 Other (specify below) CASING JOINTS: Glued Clamped Welded Threaded X

TYPE OF SCREEN OR PERFORATION MATERIAL: 1 Steel 2 Brass 3 Stainless steel 4 Galvanized steel 5 Fiberglass 6 Concrete tile 7 PVC 8 RM (SR) 9 ABS 10 Asbestos-Cement 11 Other (specify) 12 None used (open hole)

6 GROUT MATERIAL: 1 Neat cement 2 Cement grout 3 Bentonite 4 Other Concrete: 0-15' Grout Intervals From 15 ft. to 17 ft. From ft. to ft. From ft. to ft.

Table with columns: FROM, TO, LITHOLOGIC LOG, FROM, TO, PLUGGING INTERVALS. Rows include lithological descriptions like 'Grass on top; Brown silty clay' and 'Tan coarse sand'.

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 4/10/14 and this record is true to the best of my knowledge and belief.

INSTRUCTIONS: Please fill in blanks or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Bureau of Water, Geology Section, 1000 SW Jackson St., Suite 420, Topeka, Kansas 66612-1367. Telephone 785-296-5522. Send one to WATER WELL OWNER and retain one for your records.

TRITERRA

LAND SERVICES

P.O. Box 546
Clearwater, Kansas 67026
Cell (316) 648-3617 Fax (620) 584-4371
Email: triterrals@yahoo.com

SURVEYING OF MONITORING WELLS COUNTRY CORNER SOLOMON, KANSAS

The site is located in Section 18, Township 13 South, Range 1 East of the Sixth Principal Meridian, Dickinson County, Kansas. The Southeast corner of Section 18 was assigned coordinates of 00.00 North and 00.00 West.

The vertical control was a NGS BM described as a disk set in the top of a concrete monument, flush with the ground, in the town park SE of the intersection of West 4th Street and Walnut Street, 3.3 feet south of the bandstand and 24 feet east of a 16 inch pine tree. Elevation: 1171.62 ft MSL. A control point was established as a chiseled 'X' on top of the curb and west end of the radius at the southeast corner of the site.

The Latitude and Longitude were recorded from a GPS unit. The site is located on the 7.5' quad map titled "Niles".

ID	NORTH	WEST	LATITUDE	LONGITUDE	ELEVATION
SE CORNER 18-13S-1E	00.00	00.00			
CP	1431.39	4855.43	38.91833	97.37085	1171.27
MW-1 SE SW NW SW	1500.89	4868.63	38.91848	97.37089	RIM 1171.38 TOC 1171.19
MW-2 SE SW NW SW	1453.72	4896.15	38.91837	97.37097	RIM 1171.34 TOC 1170.98
MW-3 SE SW NW SW	1448.81	4856.41	38.91836	97.37085	RIM 1171.69 TOC 1171.25
MW-4 SE SW NW SW	1584.26	4888.86	38.91873	97.37096	RIM 1172.55 TOC 1172.19
MW-5 SE SW NW SW	1511.55	4774.49	38.91855	97.37057	RIM 1172.36 TOC 1171.83
MW-6 SW SW NW SW	1448.80	4974.56	38.91838	97.37127	RIM 1171.45 TOC 1170.96
MW-7 SE SW NW SW	1363.12	4868.69	38.91813	97.37092	RIM 1171.97 TOC 1171.52
MW-8 SE SW NW SW	1440.61	4725.73	38.91834	97.37039	RIM 1172.12 TOC 1171.74
MW-9 SE SW NW SW	1360.20	4758.78	38.91809	97.37051	RIM 1171.97 TOC 1171.74

