

WATER WELL RECORD Form WWC-5 KSA 82a-1212

Distance and direction from nearest town or city street address of well if located within city?

Four miles south of DeSoto, Ks.

Well # UG-2

3	LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:	4	DEPTH OF COMPLETED WELL: 33	ft.	ELEVATION: 913.8' (MSL)
			Depth(s) Groundwater Encountered	1 22	ft 2 ft 3 ft

5 TYPE OF BLANK CASING USED:

1 Steel	3 RMP (SR)	5 Wrought iron	8 Concrete tile	CASING JOINTS: Glued Clamped
② PVC	4 ABS	6 Asbestos-Cement	9 Other (specify below)	Welded
		7 Fiberglass		Threaded. X

Blank casing diameter 4 in. to 21 ft., Dia in. to ft., Dia in. to ft.

Casing height above land surface 1.2 in., weight lbs./ft. Wall thickness or gauge No.

TYPE OF SCREEN OR PERFORATION MATERIAL:

1 Steel	3 Stainless steel	5 Fiberglass	⑦ PVC	10 Asbestos-cement
2 Brass	4 Galvanized steel	6 Concrete tile	8 RMP (SR)	11 Other (specify)
			9 ABS	12 None used (open hole)

SCREEN OR PERFORATION OPENINGS ARE:

1 Continuous slot	③ Mill slot	5 Gauzed wrapped	8 Saw cut	11 None (open hole)
2 Louvered shutter	4 Key punched	6 Wire wrapped	9 Drilled holes	
		7 Torch cut	10 Other (specify)	

SCREEN-PERFORATED INTERVALS:

From 21 ft. to 33 ft.	From ft. to ft.
From ft. to ft.	From ft. to ft.

GRAVEL PACK INTERVALS:

From 16 ft. to 33 ft.	From ft. to ft.
From ft. to ft.	From ft. to ft.

FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHOLOGIC LOG
0	3	Topsoil			
3	11	Clay, silty, brown and dk brown			
11	17	Limestone, gray and lt. gray, w/sandstone			
17	20	Sandy clay, tan w/thin layers of brown limestone			
20	24	Shale, black, blocky water at 22'			
24	31	Limestone dk gray			
31	33	Shale, dk. gray, tight T.D.			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 7-25-88 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 338 This Water Well Record was completed on (mo/day/y) 6-25-89 under the business name of Jayhawk Drilling by (signature) Thomas F. Maylan

INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Office of Oil Field and Environmental Geology, Regulation and Permitting Section, Topeka, Kansas 66620-7500, Telephone: 913-862-9360. Send one to WATER WELL OWNER and retain one for your records.