

8  
USE TYPEWRITER OR BALL  
POINT PEN-PRESS FIRMLY,  
PRINT CLEARLY...

WATER WELL RECORD  
KSA 82a-1201-1215

Kansas Department of Health and  
Environment-Division of Environment  
(Water well Contractors)  
Topeka, Kansas 66620

1. Location of well:	County <b>Johnson</b>	Fraction <b>NW 1/4 SW 1/4 SW 1/4</b>	Section number <b>25</b>	Township number <b>T 13 S</b>	Range number <b>R 22</b>	<b>QW</b>
2. Distance and direction from nearest town or city: Street address of well location if in city: <b>4 mi. west of Olathe</b>			3. Owner of well: <b>Mr. Lee Vickers</b> R.R. or street: <b>2430 N. 119th</b> City, state, zip code: <b>Kansas City, Kansas</b>			
4. Locate with "X" in section below: N W E S 1 Mile			Sketch map: 6. Bore hole dia. <b>8</b> in. Completion date <b>10-31-75</b> Well depth <b>200</b> ft. 7. <input checked="" type="checkbox"/> Cable tool <input checked="" type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input type="checkbox"/> Reverse rotary 8. Use: <input checked="" type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other 9. Casing: Material <b>PL</b> Height: Above or below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface <b>18</b> in. RMP <input type="checkbox"/> PVC <input checked="" type="checkbox"/> Weight <input type="checkbox"/> lbs./ft. Dia. <b>5</b> in. to <b>200</b> ft. depth Wall Thickness: inches or Dia. <input type="checkbox"/> in. to <input type="checkbox"/> ft. depth gage No. <b>258 WT</b>			
5. Type and color of material			From	To		
Top Soil - Dark			0	2	10. Screen: Manufacturer's name <b>Vinylplex, Inc.</b> Type <b>PVC</b> Dia. <b>5"</b> Slot/gauze <b>.06 1/16</b> Length Set between <b>42</b> ft. and <b>52</b> ft. ft. and <input type="checkbox"/> ft. and <input type="checkbox"/> ft. Gravel pack? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No Size range of material <b>1/4 - 1/8</b>	
Clay - Yellow			2	20	11. Static water level: <input type="checkbox"/> mo./day/yr. <b>53</b> ft. below land surface Date <b>10-31-75</b>	
Lime - White			20	42	12. Pumping level below land surfaces: ft. after <input type="checkbox"/> hrs. pumping <input type="checkbox"/> g.p.m. ft. after <input type="checkbox"/> hrs. pumping <input type="checkbox"/> g.p.m. Estimated maximum yield <b>100 gal. day</b> g.p.m.	
Sandstone - Gray			42	52	13. Water sample submitted: <input type="checkbox"/> mo./day/yr. <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date	
Lime - White			52	72	14. Well head completion: <input checked="" type="checkbox"/> Pitless adapter <b>18</b> inches above grade	
Sandstone - Gray			72	80	15. Well grouted? <input checked="" type="checkbox"/> Yes With: <input checked="" type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input type="checkbox"/> Concrete Depth: From <b>3</b> ft. to <b>29</b> ft.	
Lime - White			80	155	16. Nearest source of possible contamination: ft. <b>100</b> Direction <b>East</b> Type <b>Septic</b> Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	
Shale - Blue			155	180	17. Pump: Not installed Manufacturer's name <b>Jacuzzi</b> Model number <b>7SLB</b> HP <b>3/4</b> Volts <b>230</b> Length of drop pipe <b>180</b> ft. capacity <b>8</b> g.p.m. Type: <input checked="" type="checkbox"/> Submersible <input type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other	
Sandstone Shale - Gray			180	195	20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <b>BREUER DRILLING CO. 174</b> Business name <b>Box 147 Basehor, Kansas</b> License No. Address <b>Box 147 Basehor, Kansas</b> Signed <b>[Signature]</b> Date <b>12-15-75</b> Authorized representative	
Shale - Blue			195	200		
(Use a second sheet if needed)						
18. Elevation: Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input type="checkbox"/> Upland <input type="checkbox"/> Valley		19. Remarks:				

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5