

A18-MW003

KSA 82a-1212

Check: ☒ White Copy, ☐ Blue Copy, ☐ Pink Copy

FIGURE 2-3

A18AW003

HTW DRILLING LOG						HOLE NO. A18 TFP 0022 04	
1. COMPANY NAME TETRA TECH			2. DRILLING SUBCONTRACTOR TSA ENVIRONMENTAL			SHEET OF SHEETS	
3. PROJECT SUNFLOWER AAP			4. LOCATION AOC 10				
5. NAME OF DRILLER AARON SENSE			6. MANUFACTURER'S DESIGNATION OF DRILL GEOPRICE 6620 DT				
7. SIZES AND TYPES OF DRILLING AND SAMPLING EQUIPMENT			8. HOLE LOCATION AOC 10 / 022003				
			9. SURFACE ELEVATION				
			10. DATE STARTED 5/1/2009		11. DATE COMPLETED 5/7/2009		
12. OVERBURDEN THICKNESS 6.5'			15. DEPTH, GROUNDWATER ENCOUNTERED 6.0' AT TIME OF DRILLING				
13. DEPTH DRILLED INTO ROCK 3.5'			16. DEPTH TO WATER AND ELAPSED TIME AFTER DRILLING COMPLETED NO WATER DETECTED AFTER WELL INSTALL				
14. TOTAL DEPTH OF HOLE 10.0'			17. OTHER WATER LEVEL MEASUREMENTS (SPECIFY)				
18. GEOTECHNICAL SAMPLES		DISTURBED		UNDISTURBED		19. TOTAL NUMBER OF CORE BOXES	
20. SAMPLES FOR CHEMICAL ANALYSIS		VOC	METALS	OTHER (SPECIFY)	OTHER (SPECIFY)	OTHER (SPECIFY)	21. TOTAL CORE REC. %
		NA	NA				
22. DISPOSITION OF HOLE		BACKFILLED	MONITORING WELL	OTHER (SPECIFY)	23. SIGNATURE OF INSPECTOR Yankovic		
LEV.	DEPTH b	DESCRIPTION OF MATERIALS c		FIELD SCREENING RESULTS d	GEOTECH SAMPLE OR CORE BOX NO. e	ANALYTICAL SAMPLE NO. f	BLOW COUNTS g
		FIAM, MOIST, VERY DARK BROWN (10 YR 2/2) LOV PLASTIC SILTY CLAY WITH ROOT MARKS		0.0 PPM			
1		STIFF, MOIST, DARK YELLOWISH BROWN (10 YR 3/4) SILTY CLAY WITH IRON OXIDE STAINING & MANGANESE MARKS		0.0 PPM	60		
2				0.0 PPM			
3				0.0 PPM			
4				0.0 PPM			
5				0.0 PPM			

FIGURE 2-3 (Continued)

A18 MW003

HTW DRILLING LOG							HOLE NO A18-TPP022-84
PROJECT SEARP		INSPECTOR KIM T. DAECH					SHEET 2
ELEV. a	DEPTH b	DESCRIPTION OF MATERIALS c	FIELD SCREENING RESULTS d	GEOTECH SAMPLE OR CORE BOX NO. e	ANALYTICAL SAMPLE NO. f	BLOW COUNTS g	REMARKS h
	6						
	6	BELOWING WET, WITH SOME	6.0 PPM	56/60			WATER DETECTED AT 6.0' AND
	7	SHALE, WEATHERED, LIGHT OLIVE GRAY (SYCL), DRY	0.0 PPM				SAMPLE COLLECTED AT 5.0-6.5'
	8		0.0 PPM				
	9		0.0 PPM				
	10	BELOWING DRY, GREENISH GRAY (CLAY 3/4) BOTTOM OF BORING 100					
	11						
	12						
	13						
W							