


1 LOCATION OF WATER WELL: County: Johnson		Fraction SE 1/4 SW 1/4 SE 1/4	Section Number 25	Township Number T 13 S	Range Number R 23 EW																																																												
Distance and direction from nearest town or city street address of well if located within city? 904 E. Sante Fe, Olathe, KS																																																																	
2 WATER WELL OWNER: Southland Corp. RR#, St. Address, Box #: 814 Baker Rd City, State, ZIP Code: Virginia Beach, VA 23462 Board of Agriculture, Division of Water Resources Application Number:																																																																	
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 		4 DEPTH OF COMPLETED WELL: 12' ft. ELEVATION: Depth(s) Groundwater Encountered 1. 8' ft. 2. ft. 3. ft. WELL'S STATIC WATER LEVEL 3.60 ft. below land surface measured on mo/day/yr 3-19-98 Pump test data: Well water was ft. after hours pumping gpm Est. Yield gpm: Well water was ft. after hours pumping gpm Bore Hole Diameter 8 1/2" in. to 12' ft. and in. to ft. WELL WATER TO BE USED AS: 5 Public water supply 8 Air conditioning 11 Injection well 1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below) 2 Irrigation 4 Industrial 7 Lawn and garden only 10 Monitoring well Was a chemical/bacteriological sample submitted to Department? Yes No X ; If yes, mo/day/yr sample was submitted Water Well Disinfected? Yes No																																																															
5 TYPE OF BLANK CASING USED: 1 Steel 3 RMP (SR) 2 PVC 4 ABS Blank casing diameter 2.375 in. to 4' ft. Dia. in. to ft. Dia. in. to SDR 13 ft. Casing height above land surface Flush Mt. in. weight lbs./ft. Wall thickness or gauge No. SCH 40 TYPE OF SCREEN OR PERFORATION MATERIAL: 1 Steel 3 Stainless steel 5 Fiberglass 8 RMP (SR) 10 Asbestos-cement 2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS 11 Other (specify) 12 None used (open hole) SCREEN OR PERFORATION OPENINGS ARE: 1 Continuous slot 3 Mill slot 5 Gauzed wrapped 8 Saw cut 11 None (open hole) 2 Louvered shutter 4 Key punched 6 Wire wrapped 9 Drilled holes 10 Other (specify) 7 Torch cut SCREEN-PERFORATED INTERVALS: From 12' ft. to 4' ft. From ft. to ft. From ft. to ft. From ft. to ft. GRAVEL PACK INTERVALS: From 12' ft. to 3' ft. From ft. to ft. From ft. to ft. From ft. to ft.		CASING JOINTS: Glued Clamped Welded Threaded X																																																															
6 GROUT MATERIAL: 1 Neat cement 2 Cement grout 3 Bentonite 4 Other Grout Intervals: From 3' ft. to 2' ft. From 2' ft. to 0' ft. From ft. to ft. From ft. to ft. What is the nearest source of possible contamination: 1 Septic tank 4 Lateral lines 7 Pit privy 10 Livestock pens 14 Abandoned water well 2 Sewer lines 5 Cess pool 8 Sewage lagoon 11 Fuel storage Fuel 15 Oil well/Gas well 3 Watertight sewer lines 6 Seepage pit 9 Feedyard 12 Fertilizer storage 16 Other (specify below) 13 Insecticide storage Direction from well? West How many feet? 25'																																																																	
<table border="1" style="width:100%; border-collapse: collapse;"> <thead> <tr> <th>FROM</th> <th>TO</th> <th>LITHOLOGIC LOG</th> <th>FROM</th> <th>TO</th> <th>PLUGGING INTERVALS</th> </tr> </thead> <tbody> <tr> <td>0</td> <td>.5</td> <td>Asphalt</td> <td></td> <td></td> <td></td> </tr> <tr> <td>.5</td> <td>2.5</td> <td>Dk gray-blk. clay, moist, no odor, firm</td> <td></td> <td></td> <td></td> </tr> <tr> <td>2.5</td> <td>8</td> <td>Brn clay w/oxide staining & gray clay mottles moist no odor, tight</td> <td></td> <td></td> <td></td> </tr> <tr> <td>8</td> <td>9.5</td> <td>Limestone, fractured, iron stained w/sandstone stringers</td> <td></td> <td></td> <td></td> </tr> <tr> <td>9.5</td> <td>12</td> <td>Yellow brn limonite stained sandstone w/gray shale stringers, dry, hard At 12' limestone</td> <td></td> <td></td> <td></td> </tr> <tr> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> </tbody> </table>						FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS	0	.5	Asphalt				.5	2.5	Dk gray-blk. clay, moist, no odor, firm				2.5	8	Brn clay w/oxide staining & gray clay mottles moist no odor, tight				8	9.5	Limestone, fractured, iron stained w/sandstone stringers				9.5	12	Yellow brn limonite stained sandstone w/gray shale stringers, dry, hard At 12' limestone																											
FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS																																																												
0	.5	Asphalt																																																															
.5	2.5	Dk gray-blk. clay, moist, no odor, firm																																																															
2.5	8	Brn clay w/oxide staining & gray clay mottles moist no odor, tight																																																															
8	9.5	Limestone, fractured, iron stained w/sandstone stringers																																																															
9.5	12	Yellow brn limonite stained sandstone w/gray shale stringers, dry, hard At 12' limestone																																																															
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed , (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 3-16-98 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 539 This Water Well Record was completed on (mo/day/yr) 3-21-98 under the business name of JB Environmental Drilling by (signature) James Becker																																																																	