

County: Johnson Fraction: NW, SW, SW, NE Sec. 36 T. 13 S R. 23 E

CORRECTION(S) to WATER WELL COMPLETION RECORD Form WWC-5 (to rectify lacking or incorrect information)

Owner: Rockwell (now The Boeing Company)

TMW-009

If location corrected, was listed as:

Section-Township-Range: not provided

Location changed to:

36-13S-23E

Fraction (¼ calls): not provided

NW, SW, SW, NE

Other changes: Initial statements: Water well record was not provided after monitoring well was completed by Kurtz Environmental on approximately Nov. 7, 1995.

Changed to: _____

Comments: Original drilling log and well construction diagram provided recently for this active well by the current environmental consultant (Haley & Aldrich) for Chemical Commodities Inc. - Olathe Site.

Verification method: Consultant verified well ID & location and provided lat/long coordinates using Google Earth (WGS 84 Horizontal Datum). Lat. 38.877905 & Long. -94.806101.

Initials: PKC Date: 1/11/2019

Submitted by: ☐ Kansas Geological Survey, Data Resources Library, 1930 Constant Ave., Lawrence, KS 66047-3724
☒ Kansas Dept. of Health & Environment, Bureau of Water, 1000 SW Jackson, Suite 420, Topeka, KS 66612-1367



GROUNDWATER
TECHNOLOGY

Drilling Log

Monitoring Well **SB027-NP [TMW-009]**

Project Rockwell/Olathe Owner Rockwell
Location Olathe, Kansas Proj. No. 042500193
Surface Elev. 1052 ft. Total Hole Depth 15.5 ft. Diameter 7.25 in.
Top of Casing -- ft. Water Level Initial -- ft. Static -- ft.
Screen: Dia 2 in. Length 10 ft. Type/Size 10 slot in.
Casing: Dia 2 in. Length 5.5 ft. Type SCH 40 PVC
Fill Material Coarse Graded RMP Sand Rig/Core CME-45/Split Barrel Continuous
Drill Co. Kurtz Environmental Method hollow stem auger
Driller Glen Kurtz Log By Tim Scott Date 11/7/95 Permit # exempt
Checked By Peter Rattery License No. CA RG 4018

See Site Map
For Boring Location

COMMENTS:

Location CC. D1510

Depth (ft.)	Well Completion	PID (ppm)	Sample ID Blow Count/ X Recovery	Graphic Log	USCS Class.	Description (Color, Texture, Structure) Trace < 10%, Little 10% to 20%, Some 20% to 35%, And 35% to 50%
-2						
0		0.5	SB027-OP 80-1			All percentages are approximate. 0-0.3, SILT (ML): 75-80% silt; 20-25% stiff, nonplastic clay; brown; damp; no stain or odor; numerous roots.
2					ML	0.3-3.5', SILT (ML): 70-75% silt; 25-30% stiff, moderately plastic clay; grayish-black; damp; no stain or odor.
4						
6					CL	3.5-9.7', LEAN CLAY (CL): 85-90% stiff, moderately plastic clay; 10-15% silt; light olive gray with light reddish-brown and minor black mottling; wet; no stain or odor.
8		0.7	SB027-OP 87-8'			
10						
12					CH	9.7-15.4', FAT CLAY (CH): >95% stiff, highly plastic clay; trace silt; light olive gray with light reddish-brown and black mottling; wet; no stain or odor.
14						
16		263	SB027-OP 14.5-15.5			15.4-15.5', REDDISH-BROWN, HIGHLY WEATHERED, ARGILLACEOUS LIMESTONE
18						
20						
22						