

LOCATION OF WATER WELL:		Fraction	Section Number	Township Number	Range Number
County: Johnson		SW ¼ NE ¼ SE ¼	35	T 13 S	R 23 E/W
Distance and direction from nearest town or city street address of well if located within city? 200 S. Kansas, Olathe, KS.					
WATER WELL OWNER: Al Spruytte's 66 RR#, St. Address, Box # : 200 S. Kansas City, State, ZIP Code : Olathe, KS. Board of Agriculture, Division of Water Resources Application Number:					
LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		DEPTH OF COMPLETED WELL .15'3" ft. ELEVATION:			
A diagram showing a section box divided into four quadrants labeled NW, SW, SE, and NE. An arrow points to the center of the box.		Depth(s) Groundwater Encountered 1. 4' ft. 2.ft. 3.ft.			
		Well's Static water level 3.40 ft. below land surface measured on mo/day/yr 4-13-95			
		Pump test data: Well water wasft. after hours pumping gpm			
		Est. Yieldgpm; Well water wasft. after hours pumping gpm			
		Bore Hole Diameter 8 1/2" in. to 15'3" ft., andin. toft.			
		WELL WATER TO BE USED AS: 1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below) 2 Irrigation 4 Industrial 7 Lawn and garden only ⑩ Monitoring well			
		Was a chemical/bacteriological sample submitted to Department? Yes.....No X; If yes, mo/day/yr sample was submitted			
		Water Well Disinfected? Yes No			
TYPE OF BLANK CASING USED:					
1 Steel		5 Wrought iron	8 Concrete tile	CASING JOINTS: Glued	Clamped
② PVC		3 RMP (SR)	9 Other (specify below)	Welded	
Blank casing diameter 2.375 in. to 5'		6 Asbestos-Cement		Threaded	X
Casing height above land surface Flush Mount weight		7 Fiberglass		SCH 13	40
TYPE OF SCREEN OR PERFORATION MATERIAL:					
1 Steel		3 Stainless steel	5 Fiberglass	8 RMP (SR)	11 Other (specify)
2 Brass		4 Galvanized steel	6 Concrete tile	9 ABS	12 None used (open hole)
SCREEN OR PERFORATION OPENINGS ARE:		5 Gauzed wrapped	8 Saw cut	11 None (open hole)	
1 Continuous slot		6 Wire wrapped	9 Drilled holes		
2 Louvered shutter		7 Torch cut,	10 Other (specify)		
3 Mill slot					
SCREEN-PERFORATED INTERVALS:		From 15' ft. to 5' ft.	From ...ft. to ...ft.	From ...ft. to ...ft.	From ...ft. to ...ft.
GRAVEL PACK INTERVALS:		From 15' ft. to 4' ft.	From ...ft. to ...ft.	From ...ft. to ...ft.	From ...ft. to ...ft.
GROUT MATERIAL:					
Grout Intervals: From 4' ft. to 3' ft.		(2) Cement grout	(3) Bentonite	4 Other	
What is the nearest source of contamination?		1 Septic tank	4 Lateral lines	7 Pit privy	10 Livestock pens
(3) In Products Island Location		2 Sewer lines	5 Cess pool	8 Sewage lagoon	11 Fuel storage
		3 Watertight sewer lines	6 Seepage pit	9 Feedyard	12 Fertilizer storage
					13 Insecticide storage
Direction from well? 0'					How many feet? 0'
FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	Ls.Rx. gravel, packed.			
2	4	Dk. blk. silty clay, moist, none-faint odor.			
4	7	Green-blue green mottled soft clay, wet, slight to mod. odor, iron oxides.			
7	15'3	Pale-med brn clay w/ gray clay & iron oxide mottling, firm, moist, no odor.			
CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 4-6-95 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 539 This Water Well Record was completed on (mo/day/yr) 4-17-95 <u>JB Environmental Drilling</u> by signature James Boker					