


1 LOCATION OF WATER WELL:		Fraction	Section Number	Township Number	Range Number
County: Johnson		SW 1/4 SW 1/4 SE 1/4	17	T 13 S	R 24 E/W
Distance and direction from nearest town or city street address of well if located within city?					
15500W. 117 st. Olathe, Ks					
2 WATER WELL OWNER: Bulger Service Center					
RR#, St. Address, Box # : 15500 W. 117 st			Board of Agriculture, Division of Water Resources		
City, State, ZIP Code : Olathe, Ks 66062			Application Number:		
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL: 10.5 ft. ELEVATION:			
		Depth(s) Groundwater Encountered 1. 9.73 ft. 2. ft. 3. ft.			
		WELL'S STATIC WATER LEVEL ft. below land surface measured on mo/day/yr			
		Pump test data: Well water was ft. after hours pumping gpm			
		Est. Yield gpm: Well water was ft. after hours pumping gpm			
		Bore Hole Diameter 6 in. to 10.5 ft., and in. to ft.			
		WELL WATER TO BE USED AS: 5 Public water supply 8 Air conditioning 11 Injection well			
		1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below)			
		2 Irrigation 4 Industrial 7 Lawn and garden only 10 Monitoring well			
		Was a chemical/bacteriological sample submitted to Department? Yes.....No.....X; If yes, mo/day/yr sample was submitted			
		Water Well Disinfected? Yes No X			
5 TYPE OF BLANK CASING USED:					
1 Steel		3 RMP (SR)	5 Wrought iron	8 Concrete tile	CASING JOINTS: Glued Clamped
2 PVC		4 ABS	6 Asbestos-Cement	9 Other (specify below)	Welded
			7 Fiberglass		Threaded. X
Blank casing diameter . 2 in. to 3.0 ft., Dia in. to ft., Dia in. to ft.					
Casing height above land surface. 3.0 ft., weight lbs./ft. Wall thickness or gauge No. SCH 40. PVC.					
TYPE OF SCREEN OR PERFORATION MATERIAL:					
1 Steel		3 Stainless steel	5 Fiberglass	7 PVC	10 Asbestos-cement
2 Brass		4 Galvanized steel	6 Concrete tile	8 RMP (SR)	11 Other (specify)
				9 ABS	12 None used (open hole)
SCREEN OR PERFORATION OPENINGS ARE:					
1 Continuous slot		3 Mill slot	5 Gauzed wrapped	8 Saw cut	11 None (open hole)
2 Louvered shutter		4 Key punched	6 Wire wrapped	9 Drilled holes	
			7 Torch cut	10 Other (specify)	
SCREEN-PERFORATED INTERVALS: From 3.0 ft. to 10.0 ft., From ft. to ft.					
GRAVEL PACK INTERVALS: From 2.5 ft. to 10.5 ft., From ft. to ft.					
6 GROUT MATERIAL: 1 Neat cement 2 Cement grout 3 Bentonite 4 Other					
Grout Intervals: From 0 ft. to 2 ft., From 2 ft. to 3 ft., From ft. to ft.					
What is the nearest source of possible contamination:					
1 Septic tank		4 Lateral lines	7 Pit privy	10 Livestock pens	14 Abandoned water well
2 Sewer lines		5 Cess pool	8 Sewage lagoon	11 Fuel storage	15 Oil well/Gas well
3 Watertight sewer lines		6 Seepage pit	9 Feedyard	12 Fertilizer storage	16 Other (specify below)
				13 Insecticide storage	
Direction from well? E				How many feet? 10'	
FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	0.4	topsoil 4"			
0.4	8.7	lean clay, silty, red brown, moist			
		firm lean clay becoming gray brown			
		mottled with trace limonite nodules at 2.0ft			
		lean clay becoming red brown with			
		limonite nodules at 6.0ft			
8.7	10.5	limestone, highly weathered, yellow			
		brown, shale stringer at 9.5 to 9.9ft			
		becoming moist at 10.0ft			
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 7-19-90 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 416 This Water Well Record was completed on (mo/day/yr) 10-8-90 under the business name of TERRACON by (signature) [Signature]					